

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1195	05-00064-00-RS	KANE	15	3
STA. 00+15.88		TO STA.	29+03.08	
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NUMBER 83795				

### SUMMARY OF QUANTITIES

CODE	PAY ITEM DESCRIPTION	UNIT	QUANTITY 1000
21101615	TOPSOIL FURNISH AND PLACE, 4'	SY	500
25000400	NITROGEN FERTILIZER NUTRIENT	LB	15
25000500	PHOSPHORUS FERTILIZER NUTRIENT	LB	15
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	15
25200110	SODDING, SALT TOLERANT	SY	500
25200200	SUPPLEMENTAL WATERING	UNIT	10
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2850
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SY	187
42001300	PROTECTIVE COAT	SY	392
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SF	1260
44000007	BITUMINOUS SURFACE REMOVAL 2'	SY	9481
44000500	COMBINATION CURB AND GUTTER REMOVAL	FT	756
44000600	SIDEWALK REMOVAL	SF	1260
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SY	9481
60300305	FRAMES AND LIDS TO BE ADJUSTED	EA	6
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FT	756
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LS	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LS	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4'	FT	685
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6'	FT	800
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12'	FT	285
* 88600600	DETECTOR LDDP REPLACEMENT	FT	228
XX004209	CLASS B PATCH, SPECIAL, 10 INCH	SY	1500
XX004238	BITUMINOUS DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SY	91
X4066424	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX "D", NS0	TON	796.4
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, NS0	TON	597.3

\* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**CITY OF BATAVIA**  
**PINE STREET**  
**SUMMARY OF QUANTITIES**

DATE: 4/12/05  
DESIGNED BY: KRY  
CHECKED BY: NAB