

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5349	04-00170-00-SP	DEKALB	17	2
COVER SHEET				
F.H.W.A. REG. 5 ILLINOIS FED. AID PROJECT				

# SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 1000-2A

PAY CODE	DESCRIPTION	UNITS	QUANTITY
20200100	EARTH EXCAVATION	CU YD	441.0
20800150	TRENCH BACKFILL	CU YD	52.0
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1112.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14.0
25200110	SODDING, SALT TOLERANT	SQ YD	1112.0
25200200	SUPPLEMENTAL WATERING	UNIT	3.0
28000500	INLET AND PIPE PROTECTION	EACH	5.0
31101800	SUB-BASE GRANULAR MATERIAL, TYPE B 10"	SQ YD	735.0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.0
40600300	AGGREGATE (PRIME COAT)	TON	23.0
40600640	LEVELING BINDER (HAND METHOD)TY 2	TON	10.0
40600990	TEMPORARY RAMPS	SQ YD	72.0
42300300	PCC DRIVEWAY PAVEMENT, 7"	SQ YD	95.0
42400200	PORT. CEMENT CONC. SIDEWALK, 5"	SQ FT	184.0
* 44000030	BIT CONC SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4236.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	156.0
44000600	SIDEWALK REMOVAL	SQ FT	62.0
44201789	CLASS D PATCH TYPE 2 12"	SQ YD	23.0
* 44213200	SAW CUTS	FOOT	901.0
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1802.0
50800105	REINFORCEMENT BARS	POUND	100.0
60107700	PIPE UNDERDRAINS, 6"	FOOT	60.0
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	2.0
* 60213300	CATCH BASIN, SPECIAL	EACH	6.0
60218300	MANHOLE, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1.0
60255500	MANHOLE TO BE ADJUSTED	EACH	13.0
60404800	FRAME AND GRATE, TYPE 11	EACH	6.0
60406000	FRAME & LID, TY-1 OPEN LID	EACH	3.0
60406100	FRAME & LID, TY-1 CLOSED LID	EACH	5.0
60500050	REMOVING CATCH BASINS	EACH	2.0
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1075.0
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	156.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	79.0
78000100	THERMOPLASTIC PAVT MK LETTERS & SYMBOLS	SQ FT	47.0
78000200	THERMOPLASTIC PAVT MK LINE ,4"	FOOT	3558.0
78000400	THERMOPLASTIC PAVT MK LINE, 6"	FOOT	819.0
78000600	THERMOPLASTIC PAVT MK LINE ,12"	FOOT	91.0
78000650	THERMOPLASTIC PAVT MK LINE,24"	FOOT	74.0
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	208.0
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	23.0
* X0321556	SANITARY MANHOLE TO BE ADJUSTED	EACH	5.0
* X0517100	STORM SEWERS, DUCTILE IRON PIPE 8"	FOOT	10.0
* X3560120	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 8"	SQ YD	553.0
* X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	517.0
* X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N50	TON	62.0
* X4066765	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N50	TON	28.0
* XX003424	CONNECTION TO EXISTING STRUCTURE	EACH	3.0

\* = NEED SPECIAL PROVISION OR DETAIL