

SCHEDULE OF QUANTITIES 1000 PARTICIPATING 6TH STREET

STORM SEWER, HDPE, 8"

LOCATION	FT
STA. 23+50	27
STA. 24+75	28
TOTAL:	55

MANHOLES, TYPE A, 4' DIA., TYPE 1 FRAME, OPEN LID

LOCATION	EACH	LOCATION	EACH
STA. 30+35	1	STA. 102+80	1
TOTAL:			
2			

MANHOLES, TYPE A, 5' DIA., TYPE 1 FRAME, OPEN LID

LOCATION	EACH	LOCATION	EACH
STA. 6+84	1	STA. 15+66	1
STA. 9+70	1	STA. 18+55	1
STA. 10+96	1	STA. 21+67	1
STA. 13+88	1	STA. 22+42	1
STA. 13+95	1	STA. 26+29	1
STA. 15+26	1	STA. 39+84	1
TOTAL:			
12			

INLETS, SPECIAL, NO. 1

LOCATION	EACH	LOCATION	EACH
STA. 39+33	1	STA. 39+99 (R)	1
STA. 39+58	1	STA. 39+99 (L)	1
TOTAL:			
4			

INLETS, SPECIAL, NO. 2

LOCATION	EACH	LOCATION	EACH
STA. 15+66	1	STA. 25+70	1
STA. 15+67	1	STA. 26+07	1
STA. 18+55 (R)	1	STA. 26+29 (R)	1
STA. 18+55 (L)	1	STA. 26+29 (L)	1
STA. 21+67	1	STA. 29+98	1
STA. 22+08	1	STA. 30+35	1
STA. 22+38	1	STA. 31+50 (R)	1
STA. 22+44	1	STA. 31+50 (L)	1
TOTAL:			
16			

AREA DRAIN

LOCATION	EACH	LOCATION	EACH
STA. 23+50	1	STA. 24+75	1
TOTAL:			
2			

TRENCH BACKFILL

LOCATION	CU YD
STA. 14+72 TO 31+50 (STM)	1378
STA. 39+57 TO 104+19 (STM)	241
STA. 101+19 TO 104+19 (STM)	297
TOTAL:	
1916	

FRAME AND GRATES TO BE ADJUSTED (SPECIAL)

LOCATION	EACH	LOCATION	EACH
STA. 35+23	1	STA. 37+04 (R)	1
STA. 36+80	1	STA. 43+53	1
STA. 37+02	1	STA. 43+54	1
STA. 37+04 (L)	1		
TOTAL:			
7			

SANITARY SERVICE ADJUSTMENT

LOCATION	EACH	LOCATION	EACH
STA. 102+07	1	STA. 103+47	1
TOTAL:			
2			

FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX

LOCATION	EACH	LOCATION	EACH
STA. 15+59	1	STA. 30+64	1
STA. 18+97	1	STA. 41+02	1
STA. 22+45	1	STA. 43+30	1
STA. 26+36	1		
TOTAL:			
7			

SCHEDULE OF QUANTITIES NON-PARTICIPATING 7TH AVENUE

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5012	02-00098-00-FP	BOONE	30	5

DRIVEWAY PAVEMENT REMOVAL

LOCATION	SQ YD	LOCATION	SQ YD
STA. 1+76	20	STA. 8+14	26
STA. 2+74	60	STA. 8+78	22
STA. 2+79	40	STA. 9+10	32
STA. 3+37	25	STA. 10+24	28
STA. 4+89	31	STA. 11+75	31
STA. 6+14	94	STA. 12+75	47
STA. 7+14 & 7+64	132	STA. 13+99	12
STA. 7+71	72		
TOTAL:			
672			

SIDEWALK REMOVAL

LOCATION	SQ FT
STA. 0+85 (L) TO 1+01 (L)	140
STA. 0+96 (R) TO 2+68 (R)	720
STA. 2+41 (L) TO 14+98 (L)	6716
STA. 3+13 (R) TO 5+63 (R)	937
STA. 13+62 (R) TO 14+10 (R)	192
STA. 14+75 (R) TO 15+01 (R)	125
STA. 15+19 (R)	72
TOTAL:	
8902	

STORM SEWER REMOVAL

LOCATION	FT
STA. 0+89 (24' L) TO 0+84 (17' R)	42
STA. 6+33 (32' L) TO 6+64 (22' L)	60
STA. 9+34 (15' R) TO 9+34 (11' L)	26
STA. 9+74 (24' R) TO 9+74 (33' R)	9
STA. 10+96 (2' R) TO 10+96 (17' L)	19
TOTAL:	
156	

REMOVING INLETS

LOCATION	EACH
STA. 11+36 (39' R)	1
TOTAL:	
1	

COMBINATION CURB AND GUTTER REMOVAL

LOCATION	FT
STA. 0+82 (L) TO 1+44 (L)	91
STA. 2+07 (R) TO 2+27 (R)	20
STA. 2+45 (L) TO 3+20 (L)	88
STA. 2+67 (R) TO 3+12 (R)	45
STA. 4+42 (L) TO 4+52 (L)	10
STA. 5+58 (L) TO 6+71 (L)	130
STA. 7+36 (L) TO 8+01 (L)	67
STA. 13+52 (R) TO 14+72 (R)	118
TOTAL:	
569	

SANITARY SEWER REMOVAL

LOCATION	FT
STA. 11+21	20
STA. 11+21 TO 15+09 (30' R)	428
STA. 15+32 TO 20+04	472
STA. 20+08 TO 36+80	1672
STA. 21+95 (CL) TO 21+95 (30' L)	30
STA. 25+85 (3' R) TO 25+85 (27' L)	30
STA. 30+15 (1' R) TO 30+15 (29' L)	30
STA. 39+78 (30' R) TO 39+78 (30' L)	60
TOTAL:	
2738	

REMOVING MANHOLES

LOCATION	EACH	LOCATION	EACH
STA. 3+63	1	STA. 8+46	1
STA. 3+64(R)	1	STA. 10+98(40' R)	1
STA. 6+33	1	STA. 11+21	1
STA. 6+45	1	STA. 15+09	1
STA. 6+61	1		
TOTAL:			
9			

VALVE BOXES TO BE REMOVED

LOCATION	EACH	LOCATION	EACH
STA. 0+78	1	STA. 11+30	1
STA. 5+80	1	STA. 11+38	1
STA. 6+45	1	STA. 15+15	1
STA. 15+57	1	STA. 29+83	1
STA. 19+48	1	STA. 30+57	1
STA. 26+00	1	STA. 40+12	1
STA. 26+05	1		
TOTAL:			
13			

WATER SERVICE REMOVAL

LOCATION	EACH	LOCATION	EACH
STA. 2+04	1	STA. 8+43	1
STA. 3+21	1	STA. 9+48	1
STA. 3+92	1	STA. 10+50	1
STA. 7+61	1	STA. 11+51	1
STA. 15+73	1	STA. 22+52	1
STA. 16+17	1	STA. 23+20	1
STA. 16+53	1	STA. 23+37	1
STA. 16+92	1	STA. 23+92	1
STA. 17+17	1	STA. 24+11	1
STA. 17+76	1	STA. 26+52	1
STA. 17+81	1	STA. 26+54	1
STA. 18+41	1	STA. 27+89	1
STA. 18+46	1	STA. 28+06	1
STA. 18+99	1	STA. 29+23	1
STA. 19+04	1	STA. 31+06	1
STA. 19+76	1	STA. 32+20	1
STA. 19+98	1	STA. 32+36	1
STA. 20+31	1	STA. 33+20	1
STA. 20+73	1	STA. 34+41	1
STA. 21+20	1	STA. 41+18	1
STA. 21+43	1	STA. 42+19	1
STA. 22+41	1		
TOTAL:			
43			

FIRE HYDRANT TO BE REMOVED

LOCATION	EACH	LOCATION	EACH
STA. 4+49	1	STA. 11+06	1
TOTAL:			
2			

BACK OF CURB REMOVAL

LOCATION	FT
STA. 0+96 TO 1+00	4
STA. 1+61 TO 1+65	4
STA. 1+85 TO 1+90	5
STA. 2+87 TO 3+93	6
STA. 14+90 TO 14+95	5
STA. 15+00 TO 15+02	5
STA. 15+19	9
TOTAL:	
38	

EARTH EXCAVATION

LOCATION	CU YD
STA. 0+54 TO 14+72	3497
TOTAL:	
3497	

SUB-BASE GRANULAR MATERIAL, TYPE B

LOCATION	CU YD
STA. 0+54 TO 14+72	200
TOTAL:	
200	

AGGREGATE BASE COURSE, TYPE B 9"

LOCATION	SQ YD
STA. 0+54 TO 14+72	5469
TOTAL:	
5469	

SUB-BASE GRANULAR MATERIAL, TYPE B 4"

LOCATION	SQ YD
STA. 0+54 TO 14+72	5469
TOTAL:	
5469	

BITUMINOUS CONCRETE SURFACE COURSE 2"

LOCATION	SQ YD
STA. 0+54 TO 14+72	5469
TOTAL:	
5469	

BITUMINOUS CONCRETE BINDER COURSE 3"

LOCATION	SQ YD
STA. 0+54 TO 14+72	5469
TOTAL:	
5469	

BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	GALS
STA. 0+54 TO 14+72	4924
TOTAL:	
4924	

ROSARIO S. TARARA		DESIGN FIRM
LAND SURVEYING, INC.		NUMBER:
3600 EAST STATE STREET, SUITE 315, ROCKFORD, IL 61108 (815)397-6333		184-002928 (35-002994)
CARROLL ENGINEERING & ASSOCIATES, P.C.		
111 W. HURLBUT AVE.		BELVIDERE, IL
TELEPHONE		(815) 547-3406
DATE: 03/24/2005	REVISION NO. & DATE:	PROJECT NO.: 372