

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	C38-DRS	MCDONOUGH	83	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	AGGREGATE (EROSION CONTROL)	AGGREGATE SHOULDERS, TYPE B	LOCATION	AGGREGATE (EROSION CONTROL)	AGGREGATE SHOULDERS, TYPE B
SOUTHBOUND	TON	TON	NORTHBOUND	TON	TON
RT STA 101+56.07 - 105+08.38	10.5		RT STA 117+47.85 - 126+22.39		20.8
RT STA 105+66.07 - 107+16.82	60.5		RT STA 126+97.44 - 150+82.02		56.6
RT STA 107+16.82 - 125+86.70		44.4	RT STA 151+63.38 - 152+73.70		2.6
RT STA 127+29.91 - 150+50.57		55.1	RT STA 152+73.70 - 152+99.45	0.7	
RT STA 152+25.45 - 153+38.70	4.4		RT STA 153+51.95 - 158+65.20	18.5	
RT STA 154+32.70 - 156+20.95	8.3		RT STA 158+65.20 - 164+54.75		14.0
RT STA 156+20.95 - 232+39.83		180.8	RT STA 165+05.51 - 179+68.54		34.7
RT STA 234+70.82 - 286+15.56		122.1	RT STA 180+56.22 - 211+84.19		74.2
RT STA 289+83.82 - 297+30		17.7	RT STA 212+35.06 - 233+24.68		49.6
LT STA 117+47.85 - 126+22.39		20.8	RT STA 234+15.12 - 250+61.03		39.1
LT STA 126+97.44 - 150+82.02		56.6	RT STA 251+11.31 - 268+85.59		42.1
LT STA 151+63.38 - 151+72.95		0.2	RT STA 269+60.20 - 286+89.98		41.1
RT STA 151+72.95 - 152+98.70	4.8		RT STA 287+79.94 - 297+30		22.5
RT STA 153+92.70 - 155+18.45	6.7		LT STA 103+82.02 - 104+82.77	3.7	
LT STA 155+18.45 - 164+54.75		22.2	LT STA 105+40.46 - 110+17.77	14.1	
LT STA 165+05.51 - 179+68.54		34.7	LT STA 110+17.77 - 125+84.69		37.2
LT STA 180+56.22 - 211+84.19		74.2	LT STA 127+18.32 - 150+52		166.2
LT STA 212+35.06 - 233+24.68		49.6	LT STA 151+84.20 - 152+47.45	2.8	
LT STA 234+15.12 - 250+61.03		39.1	LT STA 151+25.59 - 151+84.20		1.4
LT STA 251+11.31 - 268+85.59		42.1	LT STA 152+99.95 - 157+63.20	18.1	
LT STA 269+60.20 - 286+89.98		41.1	LT STA 157+63.20 - 179+62.61		52.2
LT STA 287+79.94 - 297+30		22.5	LT STA 180+80.24 - 232+80.65		123.4
SIDERROADS			LT STA 234+84.89 - 286+57.35		122.8
WEIGH STATION		4.2	LT STA 288+49.46 - 297+30		20.9
TR 85		4.3	SUB-TOTALS	57.9	921.4
TR 111		5.7			
CH 20		7.9			
TR 73		4.3			
ACCESS ROAD		2.6			
TR 93		5.3			
CH 2		4.5	COLUMN 1	95.2	866.3
TR 129		4.3	COLUMN 2	57.9	921.4
SUB-TOTALS	95.2	866.3	TOTALS	153.1	1787.7

AGGREGATE FOR DRIVEWAY MAINTENANCE	
LOCATION	TON
7 PRIVATE ENTRANCES (12' WIDE)	6.6
6 FIELD ENTRANCES (30' WIDE)	14.3
TOTAL	20.9

	AGGREGATE DITCH	PAVED DITCH REMOVAL
LOCATION	TON	FT
LT STA 147+18 - 149+06	71.4	188
TOTAL	71.4	188

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DRAWN BY
CHECKED BY