

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	138-1RS	MCDONOUGH	83	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BITUMINOUS RESURFACING - SIDEROADS							
LOCATION	AREA SHOULDER	AREA MAINLINE	BIT SURF REMOVAL BUTT JT - SHOULDER	BIT SURF REMOVAL BUTT JT - MAINLINE	BIT SURF REMOVAL (2")	BCSC SUPERPAVE IL 9.5L LE (2")	BCSC SUPERPAVE MIX D, N50 (2")
	SQ FT	SQ FT	SQ YD	SQ YD	SQ YD	TON	TON
TR 73	1024.81	5314.22	26.7	82.2	704.3	15.7	75.3
WEIGH STATION	1262.83	5620.29	26.7	123.1	764.8	18.7	83.7
TR 93	1129.21	5644.91	26.7	78.7	752.7	17.0	79.1
ACCESS ROAD	176.99	628.13	33.1	49.8	89.5	5.9	13.4
TR 85	1313.2	4828.66	26.7	82.2	682.4	19.3	69.3
CH 20	2793.24	8671.68	6.2	80.0	1273.9	35.5	116.9
TR 129	1050.64	5396.68	20.0	82.7	716.4	15.3	76.4
TR 111	1368.38	6090.98	26.6	81.9	828.8	20.0	85.0
CH 2	1021.34	5569.74	26.8	84.2	732.3	15.7	78.7
TOTALS			219.5	744.8	6545.1	163.2	677.8

TEMPORARY RAMPS	
LOCATION	SQ YD
SOUTH BOUND	
STA 105+64.32 - 105+94.32	80.0
STA 152+86.70 - 153+16.70	80.0
STA 154+10.70 - 154+40.70	80.0
STA 297+00 - 297+30	80.0
NORTH BOUND	
STA 105+59.68 - 105+89.68	80.0
STA 152+39.45 - 152+69.45	80.0
STA 153+21.95 - 153+51.95	80.0
STA 297+00 - 297+30	80.0
MEDIAN 105+61.98 - 105+91.98	43.3
WEIGH STATION	133.3
TR 73	137.8
TR 85	93.3
ACCESS RD	44.4
TR 93	122.2
TR 111	122.2
CH 2	122.2
TR 129	122.2
CH 20	122.2
TOTALS	1703.1

BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION	TON
MILLED SURFACE @ 0.1 GAL/SQ YD	
MAINLINE	40.7
SIDE ROADS, TURN LANES, CROSSOVERS	9.4
SHOULDERS	25.1
NEW BINDER @ 0.03 GAL/SQ YD	
MAINLINE	12.2
TURN LANES, CROSSOVERS	1.9
SHOULDERS	7.5
TOTAL	96.8

AGGREGATE (PRIME COAT)	
LOCATION	TON
MILLED SURFACE @ 4 LB/SQ YD	
MAINLINE	203.6
TURN LANES, SIDEROADS, CROSSOVERS	47.1
SHOULDERS	125.5
NEW BINDER @ 2 LB/SQ YD	
MAINLINE	101.8
TURN LANES, CROSSOVERS	16.0
SHOULDERS	62.8
TOTAL	556.8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DRAWN BY
CHECKED BY