

|                     |          |                  |              |           |
|---------------------|----------|------------------|--------------|-----------|
| F.A.P. RTE.         | SECTION  | COUNTY           | TOTAL SHEETS | SHEET NO. |
| 322                 | 11-10    | CHRISTIAN        | 310          | 7         |
| STA.                |          | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT |              |           |

| CODE NO. | ITEM   | SP. PROV. | UNIT  | 80% FED.<br>20% STATE<br>TOTAL<br>QUANTITIES | % FEDERAL % STATE<br>CONSTRUCTION AND SAFETY TYPE CODE |                     |  |  |  |  |  |  |  |
|----------|--|-----------|-------|--|--|---------------------|--|--|--|--|--|--|--|
|          |  |           |       |  | I000-2A<br>ROADWAY                                     | Y030-1E<br>LIGHTING |  |  |  |  |  |  |  |
| 54201297 | PIPE CULVERTS, TYPE 2 RCCP 42"   |           | FOOT  | 156  | 156  |                     |  |  |  |  |  |  |  |
| 54201303 | PIPE CULVERTS, TYPE 2 RCCP 48"   |           | FOOT  | 124  | 124  |                     |  |  |  |  |  |  |  |
| 54201489 | PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"           |           | FOOT  | 76   | 76   |                     |  |  |  |  |  |  |  |
| 54201495 | PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 30"           |           | FOOT  | 90   | 90   |                     |  |  |  |  |  |  |  |
| 54201513 | PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 48"           |           | FOOT  | 146  | 146  |                     |  |  |  |  |  |  |  |
| 54206751 | PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE, EQUIVALENT ROUND-SIZE 36"          |           | FOOT  | 198  | 198  |                     |  |  |  |  |  |  |  |
| 54207801 | PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 36" |           | FOOT  | 148  | 148  |                     |  |  |  |  |  |  |  |
| 54209475 | PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE, EQUIVALENT ROUND-SIZE 30"          |           | FOOT  | 154  | 154  |                     |  |  |  |  |  |  |  |
| 5421D018 | PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)                                 |           | FOOT  | 70   | 70   |                     |  |  |  |  |  |  |  |
| 54213465 | END SECTIONS 30"   |           | EACH  | 1  | 1  |                     |  |  |  |  |  |  |  |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"                            |           | EACH  | 16   | 16   |                     |  |  |  |  |  |  |  |
| 54213675 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"                            |           | EACH  | 4  | 4  |                     |  |  |  |  |  |  |  |
| 54213681 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"                            |           | EACH  | 4  | 4  |                     |  |  |  |  |  |  |  |
| 54213687 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"                            |           | EACH  | 2  | 2  |                     |  |  |  |  |  |  |  |
| 54214515 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"     |           | EACH  | 2  | 2  |                     |  |  |  |  |  |  |  |
| 54214521 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"     |           | EACH  | 4  | 4  |                     |  |  |  |  |  |  |  |
| 54217680 | REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 24" RISER                          |           | EACH  | 6  | 6  |                     |  |  |  |  |  |  |  |
| 54217711 | REINFORCED CONCRETE PIPE TEE, 42" PIPE WITH 24" RISER                          |           | EACH  | 1  | 1  |                     |  |  |  |  |  |  |  |
| 54244805 | INLET BOX, STANDARD 542501   |           | EACH  | 4  | 4  |                     |  |  |  |  |  |  |  |
| 54247130 | GRATING FOR CONCRETE FLARED END SECTION 24"                                    |           | EACH  | 3  | 3  |                     |  |  |  |  |  |  |  |
| 54248500 | CONCRETE HEADWALLS   |           | CU YD | 58.3   | 58.3   |                     |  |  |  |  |  |  |  |
| 60100060 | CONCRETE HEADWALL FOR PIPE DRAINS  |           | EACH  | 209  | 209  |                     |  |  |  |  |  |  |  |
| 60100915 | PIPE DRAINS 6"   |           | FOOT  | 100  | 100  |                     |  |  |  |  |  |  |  |
| 60100925 | PIPE DRAINS 8"   |           | FOOT  | 100  | 100  |                     |  |  |  |  |  |  |  |
| 60100935 | PIPE DRAINS 10"  |           | FOOT  | 100  | 100  |                     |  |  |  |  |  |  |  |
| 60100945 | PIPE DRAINS 12"  |           | FOOT  | 100  | 100  |                     |  |  |  |  |  |  |  |

4/20/2005 4:28:23 PM c:\p119\april19.dgn

| REVISIONS         |         |
|-------------------|---------|
| NAME              | DATE    |
| UNDERDRAINS - SEB | 4/19/05 |
|                   |         |
|                   |         |
|                   |         |
|                   |         |
|                   |         |
|                   |         |
|                   |         |
|                   |         |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 SHEET 4 OF 9  
 FAP 322 (US 51)  
 SECTION 11-1  
 CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB  
 DATE 3/21/05 CHECKED BY EBB