

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-10	CHRISTIAN	310	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

FINAL STRIPING / DELINEATOR SCHEDULE

LOCATION	POLYUREA PAVEMENT MARKING TYPE I							PREFORMED PLASTIC TYPE B	RAISED REFLECTIVE PAVEMENT MARKER	DELINEATORS			
	LETTERS & SYMBOLS	LINE 5"		LINE 6"	LINE 12"	LINE 24"	LINE 5"			SINGLE	DOUBLE	DOUBLE	
		WHITE SOLID	YELLOW SOLID	WHITE SOLID	YELLOW SOLID	WHITE SOLID	WHITE SKIP			1 WAY CRYSTAL	WHITE	WHITE	AMBER
SQ FT			FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH		
FAP 322	778+00.0 to 788+00.0	LT		1000.0	1000.1		286.0				3		
	783+60.0 to 796+11.5	RT	124.8	1182.6	1209.4	610.0		312.9	32		1	6	6
	788+00.0 to 796+11.5	LT		750.9	782.9			202.9	11		2		
	796+11.5 to 850+07.8	LT	124.8	5266.9	5326.1	610.0		1349.1	84	12	6	6	
		RT	124.8	5266.0	5323.7	610.0		1349.1	84	12	6	6	
	850+07.8 to 904+14.8	LT	124.8	5278.7	5334.8	610.0		1351.8	84	12	6	6	
		RT	124.8	5275.1	5333.6	610.0		1351.8	84	12	6	6	
	904+14.8 to 974+20.0	LT	124.8	6935.3	6963.7	610.0		1751.3	104	16	6	6	
	904+14.8 to 971+90.0	RT		6717.5	6748.3			1821.3	85	17			
	971+90.0 to 977+09.0	RT		519.0									
978+83.0 to 983+49.0	LT		466.0										
989+50.0 to 999+50.0	LT						250.0	13					
EX US 51	630+50.0 to 635+51.6	LT		351.6							1		
		☐			1003.2								
		RT		351.6							1		
SB TRANSITION	99+40.7 to 107+68.8	LT		828.1									
NB TRANSITION	300+00.0 to 313+89.6	LT			828.1						2		
		☐			1389.6								
		RT		1389.6							5		
TR 185	7+92.0 to 10+00.0	LT		188.3									
		☐			253.2								
		RT		154.3			26.0						
	10+00.0 to 12+04.5	LT		150.6			28.0						
		☐			248.6								
		RT		185.0									
TR 169 / CH 17	7+95.6 to 10+00.0	LT		185.0									
		☐			248.4								
		RT		150.6			28.0						
	10+00.0 to 12+04.8	LT		151.1			28.0						
		☐			249.4								
		RT		185.3									
TR 151A	7+94.9 to 10+00.0	LT		185.6									
		☐			250.0								
		RT		151.5			28.0						
	10+00.0 to 12+06.1	LT		153.0			27.0						
		☐			252.4								
		RT		186.5									
SUB-TOTALS:			748.8	43,606	42,745	3,660	956	165	9,740	581	96	36	36
TOTALS:			748.8	86,351		3,660	956	165	9,740*	581		168	

* - SEE PIPE UNDERDRAIN SCHEDULE FOR ADDITIONAL QUANTITIES

LIGHTING SCHEDULE

PAY ITEM	UNIT	TRANSITION / TR 185 INTERSECTION	TR 169 / CH 17 INTERSECTION	TR 151A INTERSECTION	PROJECT TOTAL
ELECTRIC SERVICE INSTALLATION	EACH	1	1	1	3
WOOD LIGHTING POLE, 50 FOOT, CLASS 3	EACH	8			8
CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	160	160	160	480
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1588	1171	1171	3,930
UNIT DUCT, 2*8XLP, 1*8 XLP GROUND 3/4" POLYETHYLENE	FOOT	715	1375	1375	3,465
UNIT DUCT, 2*6XLP, 1*6 XLP GROUND 1" POLYETHYLENE	FOOT	1080			1,080
AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1190			1,190
LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	18	10	10	38
LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1	1	1	3
LIGHT POLE, STEEL, 45 FT. M.H., TENON MOUNT	EACH	6	6	6	18
LIGHT POLE, STEEL, 45 FT. M.H., TENON MOUNT - TWIN	EACH	2	2	2	6
LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	6	6	6	18
LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	2	2	2	6
BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	32	32	32	96

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 STRIPING & LIGHTING
 FAP 322 (US 51)
 SECTION 11-1
 CHRISTIAN COUNTY
 SCALE: NONE
 DATE 3/17/05
 DRAWN BY SEB
 CHECKED BY EBB

3/29/2005

\\s01f1\user\0182275\user\del\area\022\striping\01.dwg