F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-10	CHRISTIAN	310	24
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIGNAGE SCHEDULE CONTINUED

ROUTE	STATION	LANE	SIDE	FACING	SIGN * MUTCD	SIZE IN X IN W	SIZE IN X IN H	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2 SQ FT	SIGN PANEL TYPE 3 SQ FT	MESSAGE	* OF POSTS	TELESCOPING STEEL SIGN SUPPORT FOOT	WOOD SIGN SUPPORT FOOT
FAP 322	894+25	NB	OUTSIDE	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.0	
			MEDIAN	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.0	
	896+07	NB	MEDIAN	SOUTH	R3-I100L	24	24	4.0			LEFT TURN LANE	1	18.1	
					M6-2L	21	15	2.2			ARROW LT			
	896+53	NB	OUTSIDE	SOUTH	R3-I100R	24	24	4.0			RIGHT TURN LANE	1	18.1	
					M6-2R	21	15	2.2			ARROW RT			
	900+25	NB	OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
			MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
	903+25	NB	OUTSIDE	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
			MEDIAN	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
	903+61		MEDIAN	WEST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4	
					R1-2	36		3.9			YIELD			
					R6-1R	36	12	3.0			ONE WAY RT			
	904+71		MEDIAN	EAST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4	
					R1-2	36		3.9			YIELD			
					R6-1R	36	12	3.0			ONE WAY RT			
	905+00	SB	OUTSIDE	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
			MEDIAN	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
	908+00	SB	OUTSIDE	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
			MEDIAN	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
	911+75	SB	OUTSIDE	NORTH	R3-I100R	24	24	4.0			RIGHT TURN LANE	1	18.1	
					M6-2R	21	15	2.2			ARROW RT			
	912+21	SB	MEDIAN	NORTH	R3-I100L	24	24	4.0			LEFT TURN LANE	1	18.1	
					M6-2L	21	15	2.2			ARROW LT			
	914+25	SB	OUTSIDE	NORTH	W10-2	36	36	9.0			SIDE ROAD W/ RR RT SYMBOL	1	18.0	
			MEDIAN	NORTH	W10-2	36	36	9.0			SIDE ROAD W/ RR RT SYMBOL	1	18.0	
	918+00		MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	14.8	
	955+00		MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	14.8	
	976+00	SB	OUTSIDE	NORTH	R2-I104	48	96			32.0	SPEED LIMIT TRUCKS OVER 3/8	1		20.8
	980+00	SB	OUTSIDE	NORTH	R2-1	48	60		20.0		SPEED LIMIT 65	1		17.8
EX US 51	630+00		RT	SOUTH	W6-1	36	36	9.0			DIVIDED HIGHWAY SYMBOL	1	18.0	
SB TRANSITION	103+00		RT	SOUTH	R4-7	36	48		12.0		KEEP RIGHT SYMBOL	1	17.8	
	105+75		RT	NORTH	W6-3	36	36	9.0			TWO-WAY TRAFFIC SYMBOL	1	18.0	
			LT	NORTH	W6-3	36	36	9.0			TWO-WAY TRAFFIC SYMBOL	1	18.0	
NB TRANSITION	303+00 TO 311+00		LT	SOUTH	W1-8	24	30	9 x 5.0			CHEVRON	9	9 x 16.3	
TR 185	5+00		RT	WEST	W10-1	36		7.1			RAIL GRADE CROSSING SYMBOL	1	16.8	
	9+10		LT	EAST	W10-1	36		7.1			RAIL GRADE CROSSING SYMBOL	1	16.8	
	9+10		RT	EAST	R6-1L	36	12	3.0			ONE WAY LT	2	38.6	
				WEST	R6-1R	36	12	3.0			ONE WAY RT			
				WEST	R1-1	36	36	9.0			STOP			
				WEST	R6-3a	24	18	3.0			DIVIDED HIGHWAY			
	10+90		LT	WEST	R6-1L	36	12	3.0			ONE WAY LT	2	38.6	
				EAST	R6-1R	36	12	3.0			ONE WAY RT			
				EAST	R1-1	36	36	9.0			STOP			
				EAST	R6-3a	24	18	3.0			DIVIDED HIGHWAY			
TR 169 / CH 17	5+00		RT	WEST	W10-1	36		7.1			RAIL GRADE CROSSING SYMBOL	1	16.8	
	9+10		LT	EAST	W10-1	36		7.1			RAIL GRADE CROSSING SYMBOL	1	16.8	
	9+10		RT	EAST	R6-1L	36	12	3.0			ONE WAY LT	2	38.6	
				WEST	R6-1R	36	12	3.0			ONE WAY RT			
				WEST	R1-1	36	36	9.0			STOP			
				WEST	R6-3a	24	18	3.0			DIVIDED HIGHWAY			
	10+90		LT	WEST	R6-1L	36	12	3.0			ONE WAY LT	2	38.6	
				EAST	R6-1R	36	12	3.0			ONE WAY RT			
				EAST	R1-1	36	36	9.0			STOP			
				EAST	R6-3a	24	18	3.0			DIVIDED HIGHWAY			
TR 151A	5+00		RT	WEST	W10-1	36		7.1			RAIL GRADE CROSSING SYMBOL	1	16.8	
	9+10		LT	EAST	W10-1	36		7.1			RAIL GRADE CROSSING SYMBOL	1	16.8	
	9+10		RT	EAST	R6-1L	36	12	3.0			ONE WAY LT	2	38.6	
				WEST	R6-1R	36	12	3.0			ONE WAY RT			
				WEST	R1-1	36	36	9.0			STOP			
				WEST	R6-3a	24	18	3.0			DIVIDED HIGHWAY			
	10+90		LT	WEST	R6-1L	36	12	3.0			ONE WAY LT	2	38.6	
				EAST	R6-1R	36	12	3.0			ONE WAY RT			
				EAST	R1-1	36	36	9.0			STOP			
				EAST	R6-3a	24	18	3.0			DIVIDED HIGHWAY			
SERVICE DR 904	79+80		RT	SOUTH	R1-1	36	36	9.0			STOP	1	16.8	
TOTALS:								676.4	196.0	64.0			1,726.5	155.4

PERMANENT BARRICADES

LOCATION	NUMBER
FE STA 714+45	8
FE STA 723+00	8
FE STA 772+04	4
TR 193 INTERSECTION	28
ACCESS DRIVE 758	8
TOTALS:	**56**

RELOCATE SIGN PANEL - TYPE 1

LOCATION	SIGN	SQ FT
TR 185	R1-1 "STOP" 36"x36"	9.0
TR 169 / CH 17	R1-1 "STOP" 36"x36"	9.0
TOTALS:		**18.0**

REVISIONS NAME	DATE
CHEVRONS - SEB	4/1/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SIGNAGE
FAP 322 (US 51)
SECTION 11-1
CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB

DATE 3/17/05 CHECKED BY EBB

4/1/2005

p:\Files\80829\contplans\824sch01.dgn