MKS 2/8/05 \94652d\d0210lpa.dgn SUP REV: 05-04-98 SOQ 2

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(101Z)W,RS	WHITE/ EDWARDS	198	6
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 94652

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	80% FED./20% STATE		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		WHITE COUNTY 1000-2A	EDWARDS COUNTY 1000-2A	50% STATE 50% CITY WHITE SFTY-1B	50% STATE 50% CITY EDWARDS SFTY-1B		100% CITY EDWARDS SFTY-1B
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.2	0.8				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	431	431					
40600990	TEMPORARY RAMP	SQ YD	124	72	52				
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	2346	327	2019				
42001200	PAVEMENT FABRIC	SQ YD	2346	327	2019				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	586	63	523				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	4457	504	3953				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	27118	4293	6780	275	15770		
42400615	TEMPORARY SIDEWALK	SQ YD	300	150	150				
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	16631	3270	13361				
44000100	PAVEMENT REMOVAL	SQ YD	2668	846	1822				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2101	468	1633				
44000300	CURB REMOVAL	FOOT	301		301				
44000400	GUTTER REMOVAL	FOOT	6646	732	5914				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1546	948	598				
44000600	SIDEWALK REMOVAL	SQ FT	12598	2192	7198				3208
44003100	MEDIAN REMOVAL	SQ FT	1447		1447				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	13743		13743				
44004000	PAVED DITCH REMOVAL	FOOT	8		8				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	889		889				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	333		333				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	143		143				
50102400	CONCRETE REMOVAL	CU YD	17.2		17.2				
50105220	PIPE CULVERT REMOVAL	FOOT	340		340				
50300220	CLASS MS CONCRETE	CU YD	8.3		8.3				
50800105	REINFORCEMENT BARS	POUND	292	44	248				
51000105	PIPE HANDRAIL	FOOT	306		306				
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1					
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2		2				
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	1		1				

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

\94652d\d0210lpa.dgn MKS 2/8/05