

# SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	11012W,RS	WHITE/EDWARDS	198	7
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT NO.	
CONTRACT NO. 94652				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	80% FED./20% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		WHITE COUNTY 1000-2A	EDWARDS COUNTY 1000-2A	50% STATE 50% CITY WHITE SFTY-1B	50% STATE 50% CITY EDWARDS SFTY-1B			100% CITY EDWARDS SFTY-1B
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2		2					
54002070	EXPANSION BOLTS 3/4 INCH X 15 INCH	EACH	48	8	40					
54010303	PRECAST CONCRETE BOX CULVERT 3' X 3'	FOOT	72.5	58.5	14					
54010404	PRECAST CONCRETE BOX CULVERT 4' X 4'	FOOT	73.5		73.5					
54010504	PRECAST CONCRETE BOX CULVERT 5' X 4'	FOOT	42		42					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	1	2					
54216185	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER	EACH	1		1					
54216555	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 15" RISER	EACH	11	1	10					
54216560	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 15" RISER	EACH	3		3					
54216570	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 15" RISER	EACH	2		2					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	89		89					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	26		26					
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	2430	158	2272					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	418		418					
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	360		360					
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	651		651					
* 550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	52		52					
* 550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	211		211					
* 550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	1296	233	1063					
* 550A2550	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 21"	FOOT	73		73					
* 550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	182		182					
55100500	STORM SEWER REMOVAL 12"	FOOT	1218		1218					
55100700	STORM SEWER REMOVAL 15"	FOOT	89	74	15					
55100900	STORM SEWER REMOVAL 18"	FOOT	853		853					
55101200	STORM SEWER REMOVAL 24"	FOOT	47	47						
551B0100	STORM SEWER INSTALLATION, CLASS B 4"	FOOT	16		16					
551B0200	STORM SEWER INSTALLATION, CLASS B 6"	FOOT	16		16					

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

1 2 3 4 5 6 7 8 9  
 10 11 12 13 14 15 16 17 18  
 19 20 21 22 23 24 25 26 27  
 28 29 30 31 32 33 34 35 36  
 37 38 39 40 41 42 43 44  
 45 46 47 48 49 50 51 52 53  
 54 55 56 57 58 59 60 61 62 63  
 MKS 2/8/05  
 \94652\d0210ipa.dgn  
 SUP REV: 05-04-98  
 SOO 3

\94652\d0210ipa.dgn  
 MKS 2/8/05