

1 2 3 4 5 6 7 8 9 3/25/2005
 c:\projects\94652\94652.dwg
 REV: REMSCH

c:\projects\94652\94652.dwg
 steffenmk\p\ DATE

FAP 332	SECTION (101Z)W,RS	COUNTY WHITE/ EDWARDS	TOTAL SHEETS 198	SHEET NO. 17
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	
CONTRACT NO. 94652				

TREE REMOVAL SCHEDULE					
STATION	OFFSET		TREE REMOVAL 6 TO 15	TREE REMOVAL OVER 15	
5+80	29 FT	LT		33	
10+90	50 FT	RT		18	
10+80	25 FT	RT		41	
11+00	75 FT	RT		24	
11+05	80 FT	RT	12		
11+06	90 FT	RT	10		
11+07	28 FT	RT		36	
11+10	80 FT	RT	6		
11+10	90 FT	RT	6		
11+11	90 FT	RT	6		
11+13	28 FT	RT	12		
11+15	29 FT	RT	15		
11+20	95 FT	RT	8		
11+20	98 FT	RT	10		
11+20	102 FT	RT		20	
11+20	98 FT	RT		16	
11+22	28 FT	RT		16	
11+24	30 FT	RT	8		
11+25	75 FT	RT	10		
11+25	110 FT	RT	10		
11+25	113 FT	RT	10		
11+30	48 FT	RT		24	
11+32	32 FT	RT	14		
11+34	28 FT	RT		16	
11+44	48 FT	RT	8		
11+48	35 FT	RT	15		
11+49	50 FT	RT	15		
11+58	30 FT	RT	12		
11+66	25 FT	RT	12		
11+70	51 FT	RT		20	
11+70	28 FT	RT	14		
11+70	40 FT	RT	12		
11+74	32 FT	RT	12		
11+78	40 FT	RT		20	
11+82	50 FT	RT	15		
11+87	50 FT	RT	15		
11+94	28 FT	RT		16	
12+10	32 FT	RT		34	
12+25	80 FT	RT		24	
12+25	110 FT	RT	12		
12+28	30 FT	RT	5		
WHITE COUNTY TOTALS				284	358
12+35	32 FT	RT		36	
12+50	75 FT	RT		30	
12+50	100 FT	RT		18	
12+50	115 FT	RT		42	
12+52	50 FT	RT		24	
12+78	30 FT	RT	6		
12+80	25 FT	RT	14		
12+90	30 FT	RT	8		
12+92	35 FT	RT	12		
12+95	25 FT	RT	11		
12+98	23 FT	RT	8		
14+20	35 FT	RT		23	
14+20	42 FT	RT	15		
14+20	46 FT	RT		28	
15+25	50 FT	RT		39	
16+30	50 FT	RT		17	
16+50	55 FT	RT		35	
16+75	30 FT	RT	8		
15+40	27 FT	LT	8		
15+59	27 FT	LT	8		
15+98	24 FT	LT		31	
16+06	31 FT	LT		34	
16+55	35 FT	LT		42	
20+48	30 FT	RT		26	
20+67	30 FT	RT	10		
24+05	27 FT	LT		28	
24+45	36 FT	LT		51	
29+80	33 FT	RT	15		
EDWARDS COUNTY TOTAL				123	504
TOTALS				407	862

STORM SEWER REMOVAL, 12 IN				
				LENGTH
14+20	11' LT	16+55	46' LT	235
16+48	11' LT	16+60	45' LT	35
16+48	11' RT	17+00	50' RT	60
16+70	11' RT	17+00	50' RT	50
16+48	11' RT	16+70	50' LT	40
22+20	16' LT	22+20	40' LT	24
22+20	16' LT	24+50	16' LT	230
14+55	16' LT	19+52	15' LT	497
19+81	17' LT	19+82	64' LT	47
TOTAL				1218 FT

STORM SEWER REMOVAL, 15 IN					
				LENGTH	
8+40	24' LT TO	8+74	24' LT	34	
12+20	15' RT TO	12+20	55' RT	40	
EXISTING OUTLET @ 28+04				13' RT	15
TOTAL				89 FT	

STORM SEWER REMOVAL, 18 IN				
				LENGTH
19+52	15' LT TO	28+05	16' RT	853
TOTAL				853 FT

STORM SEWER REMOVAL, 24 IN				
				LENGTH
8+74	24' LT TO	8+74	23' RT	47
TOTAL				47 FT

CONCRETE REMOVAL PIPE HANDRAIL / CLASS MS CONCRETE					
ITEM	SIDE	STATION	CONC. REM (CU YD)	PIPE HANDRAIL (FOOT)	CLASS MS CONC. (CU YD)
STEPS	RT	14+15	2.7		
**STEPS	LT	14+90	2.5	88.5	3.5
STEPS	RT	15+50	2.7		
STEPS	LT	22+75	1.5	43.4	0.95
RET. WALL	LT	24+25	0.2		
STEPS	LT	15+95	1.4	43.4	0.95
C. FNDATION	LT	21+00	3.7		
STEPS	LT	24+65	1.3	43.4	0.95
STEPS	LT	26+64	0.4		
STEPS	LT	27+08	0.4	43.4	0.95
STEPS	RT	29+90	0.4	43.4	0.95
EDWARDS COUNTY TOTAL			17.2	306	8.3

** TREAD WIDTH IS 28"

PIPE CULVERT REMOVAL				
STATION	TO STATION	OFFSET		LENGTH
28+00	TO 28+00	32' LT		30
35+35	TO 35+80	27' LT		45
35+95	TO 36+18	27' LT		24
36+47	TO 36+80	28' LT		33
37+45	TO 37+74	28' LT		29
39+00	TO 39+25	27' LT		25
40+53	TO 40+82	27' LT		29
41+14	TO 41+43	27' LT		29
42+05	TO 42+30	27' LT		25
43+12	TO 43+54	27' LT		42
45+15	TO 45+44	27' LT		29
TOTAL				340

REMOVING INLETS						
REMOVING INLETS TO MAINTAIN FLOW						
REMOVING MANHOLES						
REMOVING MANHOLES TO MAINTAIN FLOW						
SIDE	STATION	OFFSET	QUANTITY	PAY ITEM		
LT.	8+74	24 FT	1	C		
RT.	8+74	24 FT	1	D		
LT.	11+48	45 FT	1	B		
RT.	12+20	13 FT	1	A		
LT.	14+20	11 FT	1	A		
RT.	16+48	12 FT	1	A		
LT.	16+48	12 FT	1	A		
RT.	18+78	18 FT	1	D		
LT.	22+19	23 FT	1	D		
LT.	22+22.5	15 FT	1	D		
LT.	22+24	26 FT	1	A		
LT.	22+62	14 FT	1	C		
LT.	16+12	23 FT	1	A		
LT.	16+17	16 FT	1	C		
LT.	16+42	21 FT	1	A		
LT.	16+46	16 FT	1	C		
RT.	19+52	12 FT	1	A		
LT.	19+52	12 FT	1	A		
RT.	19+54	12 FT	1	A		
LT.	19+54	12 FT	1	A		
LT.	19+80	16 FT	1	C		
LT.	20+19	14 FT	1	C		
RT.	22+54	13 FT	1	A		
LT.	22+54	13 FT	1	A		
LT.	22+54	15 FT	1	C		
LT.	28+04	13 FT	1	A		
RT.	28+04	12 FT	1	A		
RT.	28+04	13 FT	1	C		
TOTALS			A	B	C	D
			15	1	8	4

FRAMES AND LIDS TO BE ADJUSTED			
SIDE	STATION	OFFSET	QUANTITY
LT.	5+08	1 FT	1
WHITE COUNTY TOTAL			1
LT.	16+09	19 FT	1
LT.	20+17	12 FT	1
LT.	24+22	20 FT	1
LT.	18+05	18 FT	1
LT.	22+15	16 FT	1
LT.	26+85	16 FT	1
EDWARDS COUNTY TOTAL			6
PROJECT TOTAL			7 EACH

TREE PRUNING			
SIDE	STATION	OFFSET	QUANTITY
RT	19+10	40 FT	2
RT	19+30	40 FT	1
TOTAL			3

TRENCH BACKFILL FOR STORM SEWER REMOVAL									
				PIPE SIZE	LENGTH	BACKFILL LENGTH	BACKFILL WIDTH	BACKFILL DEPTH	TRENCH BACKFILL
12+20	15' RT TO	12+20	55' RT	15	0	14	2.75	3.75	5.3
WHITE COUNT									5
14+20	11' LT TO	16+55	46' LT	12	235	110	2.5	2	20.4
16+48	11' LT TO	16+60	45' LT	12	35	10	2.5	2	1.9
16+48	11' RT TO	17+00	50' RT	12	60	25	2.5	2	4.6
16+70	11' RT TO	17+00	50' RT	12	50	22	2.5	2	4.1
22+20	16' LT TO	22+20	40' LT	12	24	24	2.5	2	4.4
22+20	16' LT TO	24+50	16' LT	12	230	230	2.5	2	42.6
14+55	16' LT TO	19+52	15' LT	12	497	497	2.5	2	92.0
19+52	15' LT TO	28+05	16' RT	18	853	853	3	4	379.1
EXISTING OUTLET @ 28+04				13' RT	15	10	2.75	3.75	3.8
EXISTING OUTLET @ 53+30				25' RT					4.0
EDWARDS COU									557
TRENCH BACK									562

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT. HORIZ. DATE		REMOVAL SCHEDULES
DRAWN BY CHECKED BY		

REVISED 3/31/05