FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(101Z)W,RS	WHITE/ EDWARDS	198	18
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 94652

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	PROPOSED PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	LEVELING BINDER (MACHINE METHOD), SUPERPAVE NTO	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", NTO	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	BITUMINOUS SURFACE REMOVAL 2 1/4"	SUB-BASE GRANULAR MATERIAL, TYPE C	PCC BASE COURSE WIDENING, 9"
	FOOT	FOOT	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD
WHITE COUNTY												
NORTH STREET												
EAST	25.00	VAR	162.0	16	0.3	3	14	162				
WEST	30.00	VAR	137.6	14	0.3	3	12	138				
ILLINOIS ROUTE 1												
848+85 TO 849+15	30.00	VAR	131.4	13	0.3	3	11	131				
849+15 TO 849+30	15.00	VAR	84.1	8	0.2	4	7		84			
STA. EQ. 849+30 BK = 4+93.03 AH												
4+93.03 TO 5+92	98.97	VAR	453.0	45	0.9	19	38		453			
5+92 TO 8+38	246.00	38.0	1038.7	104	2.1	44	87		1039			1
8+38 TO 8+50	12.00	VAR	40.9	4	0.1	2	3		41			4
8+50 TO 12+28	378.00	26.0	1092.0	109	2.2	46	92		1092		32	229
DIVISION ST.												
2+00 TO 3+82.4	182.40	VAR	561.9	56	1.1	107	47		562			
WHITE COUNTY TOTALS				370	7.4	230	311	431	3271	0	32	234
EDWARDS COUNTY												
DIVISION ST.												
2+00 TO 3+82.4	182.40	VAR	561.9	56	1.1	108	47		562			
ILLINOIS ROUTE 1												
12+28 TO 12+50	22.00	26.0	63.6	6	0.1	3	5		64		2	15
12+50 TO 13+50	100.00	26.0	288.9	29	0.6	21	24		289		9	67
13+50 TO 16+50	300.00	26.0	866.7	87	1.7	36	73		867		26	200
16+50 TO 17+00	50.00	26.0	144.4	14	0.3	9	12		144		4	33
17+00 TO 21+50	450.00	26.0	1300.0	130	2.6	55	109		1300		39	300
21+50 TO 22+00	50.00	26.0	144.4	14	0.3	12	12		144		4	33
22+00 TO 24+50	250.00	26.0	722.2	72	1.4	30	61		722		21	167
STA. EQ. 24+50 BK = 14+55.09 AH											0	
14+55 TO 19+50	494.91	26.0	1429.7	143	2.9	60	120		1430		42	330
19+50 TO 20+00	50.00	26.0	144.4	14	0.3	7	12		144		4	33
20+00 TO 27+00	700.00	26.0	2022.2	202	4.0	85	170		2022		60	467
27+00 TO 27+50	50.00	26.0	144.4	14	0.3	11	12		144		4	33
27+50 TO 28+00	50.00	26.0	144.4	14	0.3	22	12		144		4	33
28+00 TO 28+50	50.00	26.0	144.4	14	0.3	17	12		144		4	33
28+50 TO 29+00	50.00	26.0	144.4	14	0.3	7	12		144		4	33
29+00 TO 30+50	150.00	26.0	433.3	43	0.9	18	36		433		13	100
30+50 TO 32+00	150.00	26.0	433.3	43	0.9	24	36		433		13	100
32+00 TO 34+25	225.00	26.0	650.0	65	1.3	27	55		650		19	150
34+25 TO 34+50	25.00	26.0	72.2	7	0.1	3	6		72			17
34+50 TO 35+50	100.00	26.0	288.9	29	0.6	18	24		289			67
35+50 TO 44+75	925.00	26.0	2672.2	267	5.3	112	224		2672			617
44+75 TO 46+25	150.00	26.0	433.3	43	0.9	18	36		433			100
46+25 TO 46+65	40.00	25.0	111.1	11	0.2	5	9		111			
46+65 TO 48+68	203.00	27.5	620.3	62	1.2	26	52			620		
48+68 TO 50+68	200.00	36.5	811.1	81	1.6	34	68			811		
50+68 TO 52+00	132.00	44.0	645.3	65	1.3	27	54			645		
52+00 TO 58+00	600.00	46.0	3066.7	307	6.1	129	258			3067		
58+00 TO 59+00	100.00	45.5	505.6	51	1.0	21	42			506		
59+00 TO 60+00	100.00	43.0	477.8	48	1.0	20	40			478		
60+00 TO 61+00	100.00	38.5	427.8	43	0.9	18	36			428		
61+00 TO 61+80	80.00	33.5	297.8	30	0.6	13	25			298		
61+80 TO 62+95	115.00	28.5	364.2	36	0.7	15	31			364		
62+95 TO 63+25	30.00	26.0	86.7	9	0.2	4	7			87		
ILLINOIS ROUTE 130												
0+24 TO 1+08	84.00	VAR.	711.50	71	1.4	30	60			712		
EDWARDS COUNTY TOTALS				2081	41.6	1045	1795	0	13361	8016	272	2928
PROJECT TOTALS				2452	49.0	1275	2106	431	16631	8016	304	3162

TEMPORARY RAMP

LOCATION	DEPTH OF MILL (INCH)	WIDTH (FOOT)	LENGTH (FOOT)	QUANTITY (SQ YD)
WHITE COUNTY				
NORTH STREET				
EAST	1.50	52	5.00	29
WEST	1.50	34	5.00	19
ILLINOIS ROUTE 1				
848+85	1.50	34	5.00	19
DIVISION STREET				
2+00	1.50	10	5.00	6
WHITE COUNTY TOTAL				72
EDWARDS COUNTY				
DIVISION STREET				
2+00	1.50	10	5.00	6
ILLINOIS ROUTE 1				
63+25	2.25	26	7.50	22
ILLINOIS ROUTE 130				
1+08	2.25	30	7.5	25
EDWARDS COUNTY TOTAL				52
PROJECT TOTAL				124

COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24

STATION TO STATION	QUANTITY LT FOOT	QUANTITY RT FOOT
WHITE COUNTY		
5+26 TO 8+92	386	378
8+92 TO 12+38	436	340
WHITE COUNTY TOTALS	822	718
EDWARDS COUNTY		
12+38 TO 14+46	267	225
14+46 TO 18+64	423	419
18+64 TO 22+40	331	358
22+40 TO 24+50	234	215
STA. EQ. 24+50 BK = 14+55.09 AH		
14+55 TO 16+26	135	185
16+26 TO 20+00	359	382
20+00 TO 30+25	1047	1104
30+25 TO 35+70	769	569
35+70 TO 46+64	1084	1027
53+27 TO 53+33		6
EDWARDS COUNTY TOTALS	4649	4490
PROJECT TOTAL	10679	

INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50

SIDE	STATION	QUANTITY
LT	5+00	4.8
RT	5+00	7.6
LT	8+92	3.2
RT	8+92	3.1
LT	12+38	3.8
WHITE CO. TOTAL		22.4
LT	12+38	1.5
LT	18+64	2.9
RT	18+64	2.9
LT	22+40	2.8
RT	22+40	3.2
LT	16+26	3.8
RT	54+45	10.1
EDWARDS CO. TOTAL		27.3
PROJECT TOTAL		50 TON

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06

SIDE	STATION TO STATION	QUANTITY FOOT
WHITE COUNTY		
LEFT	8+37 TO 8+65	28
LEFT	9+08 TO 9+75	67
LEFT	10+09 TO 10+68	59
LEFT	11+02 TO 11+75	82
WHITE COUNTY TOTALS		236
EDWARDS COUNTY		
LEFT	12+71 TO 13+69	136
LEFT	16+57 TO 16+82	51
LEFT	17+15 TO 17+52	37
RIGHT	16+57 TO 17+98	159
EDWARDS COUNTY TOTALS		383
PROJECT T		619

BITUMINOUS BASE COURSE SUPERPAVE 4 1/4"

STATION TO STATION	WIDTH	WIDTH	LENGTH	QUANTITY
48+69 TO 49+00	2.0	5.0	31	12.1
55+26 TO 55+96	6.5	6.5	70	50.6
55+96 TO 56+11	6.5	2	15	7.1
56+81 TO 57+00	2.5	10.5	19	13.7
57+00 TO 57+30	10.5	17	30	45.8
57+30 TO 57+46	17	18.5	16	31.6
EDWARDS COUNTY TOTAL				160.8
TOTAL				161 SQ YD

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

RESURFACING SCHEDULES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

c:\projects\94652d\d0210lpa.dgn
streffenmk "4" DATE
c:\projects\94652d\d0210lpa.dgn 1/31/2005
REV.
RESSCH