

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		*X080-2A		Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN	
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	685	657	28						
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	739	504	235						
20100500	TREE REMOVAL, ACRES	ACRE	3.9	0.3	3.6						
20101000	TEMPORARY FENCE	FOOT	1500	1500							
20200100	EARTH EXCAVATION	CU YD	57,161	28,226	28,935						
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	356	12	344						
20200400	EARTH EXCAVATION (SPECIAL)	CU YD	14,788							14,788	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,282	2,282							
20300100	CHANNEL EXCAVATION	CU YD	3,724	3,724							
20400800	FURNISHED EXCAVATION	CU YD	786	786							
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,077			568	509				
20800150	TRENCH BACKFILL	CU YD	200	97	103						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	9925		9925						
2101500	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	15,912	13,639	2,273						
25000210	SEEDING, CLASS 2A	ACRE	12.7	9.3	3.4						
25000312	SEEDING, CLASS 4A	ACRE	5.4	4.0	1.4						
25000314	SEEDING, CLASS 4B	ACRE	2.4	2.4							
25000320	SEEDING, CLASS 5	ACRE	5.4	4.0	1.4						
25000324	SEEDING, CLASS 5B	ACRE	2.4	2.4							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,845	1,413	432						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,845	1,413	432						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,845	1,413	432						
25000700	AGRICULTURAL GROUND LIMESTONE	TON	41.0	31.4	9.6						
25100120	MULCH, METHOD 2	TON	41.0	31.4	9.6						
25100630	EROSION CONTROL BLANKET	SQ YD	1644	110	1534						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,050	1,570	480						
28000300	TEMPORARY DITCH CHECKS	EACH	152	99	53						
28000400	PERIMETER EROSION BARRIER	FOOT	2808	2228	580						
28000500	INLET AND PIPE PROTECTION	EACH	30	15	15						
28100107	STONE RIPRAP, CLASS A4	SQ YD	7188	2,812	1,071	2,295	1,010				
28200100	FILTER FABRIC	SQ YD	7683	2,812	1,566	2,295	1,010				
28400100	GABIONS	CU YD	603	12	591						
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	40,535	36,570	3,965						
30201500	LIME	TON	1021.5	921.5	100.0						
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1999	971	1,028						
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	9925		9925						
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	3407	2528	879						
35101400	AGGREGATE BASE COURSE, TYPE B	TON	312	193	119						
40200700	AGGREGATE SURFACE COURSE, TYPE A, 8"	SQ YD	510	510							
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	252	227	25						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	32,129	23,138	8,991						
40600300	AGGREGATE (PRIME COAT)	TON	146	97	49						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	209	209							

NOTE:

RURAL STA. 942+50.00 TO STA. 1016+00.00
 URBAN STA. 1016+00.00 TO STA. 46+80.05

* DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SUMMARY OF QUANTITIES
SHEET 1 OF 6

DRAWN BY ASB
CHECKED BY SJK

DATE 8/02

Rev.