

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	273	7

FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT
 *107WRS-1, 107BY, 107BY-1 & 107B-2

CONTRACT NO. 94827

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		1000-2A	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE I, 12"	FOOT	51		51					
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE I 18"	FOOT	21		21					
550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE I 24"	FOOT	342		342					
55100500	STORM SEWER REMOVAL 12"	FOOT	8		8					
55100700	STORM SEWER REMOVAL 15"	FOOT	52	43	9					
55100900	STORM SEWER REMOVAL 18"	FOOT	126	126						
55101100	STORM SEWER REMOVAL 21"	FOOT	331	331						
55101200	STORM SEWER REMOVAL 24"	FOOT	638	11	627					
55101900	STORM SEWER REMOVAL 48"	FOOT	50	50						
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	490							490
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	15	7	8					
60100905	PIPE DRAINS 4"	FOOT	320						320	
60100945	PIPE DRAINS 12"	FOOT	261	140	121					
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	238	102	136					
60109520	PIPE UNDERDRAINS, FABRIC LINED TRENCH 6"	FOOT	6464	2,660	2,981					823
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1		1					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1					
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1		1					
60222805	MANHOLES, TYPE A, 5'-DIAMETER WITH MEDIAN INLET (604106)	EACH	1		1					
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1					
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1		1					
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1		1					
60246605	MEDIAN INLET (604101)	EACH	1		1					
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	2		2					
60266600	VALVES BOXES TO BE ADJUSTED	EACH	3	3						
60266700	VALVE BOXES TO BE RECONSTRUCTED	EACH	1	1						
60500040	REMOVING MANHOLES	EACH	8	2	6					
60500060	REMOVING INLETS	EACH	9		9					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	14.0		14.0					
60602500	CONCRETE GUTTER, TYPE A	FOOT	1,465		1,465					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,026	214	812					
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SQ FT	152	152						
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	4	2	2					
60900515	CONCRETE THRUST BLOCKS	EACH	4	2	2					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	812.5	400	412.5					
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	91	67	24.0					
* 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4	4						
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4	4					
* 63100167	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)	EACH	5	2	3					
63200310	GUARDRAIL REMOVAL	FOOT	717	338	379					
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	56	53	3					
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	8	5	3					

NOTE:
 RURAL STA. 942+50.00 TO STA. 1016+00.00
 URBAN STA. 1016+00.00 TO STA. 46+80.05
 * DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES SHEET 4 OF 6

DRAWN BY ASB
CHECKED BY SJK