

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	273	9

FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT

\*107WRS-1, 107BY, 107BY-1 & 107B-2

CONTRACT NO. 94827

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		<del>X000-2A</del>	Y007	
				RURAL	URBAN	RURAL	URBAN	<del>RURAL</del>	RURAL	URBAN
Z0031301	JACKING AND CRIBBING, LOCATION NO. 1	L SUM	1							
Z0031302	JACKING AND CRIBBING, LOCATION NO. 2	L SUM	1			1				
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	3,568	1,614	1,954					
<del>Z0043900</del>	<del>PREFORMED JOINT FILLER</del>	<del>FOOT</del>	<del>780</del>		<del>780</del>					
* Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1		1					
* Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM	1		1					
Z0075300	TIE BARS	EACH	391		391					
⊙ Z0076600	TRAINEES	hour	1,000	500	500					
XX000610	RELOCATE EXISTING MAILBOX	EACH	18	9	9					
XX003915	BRICK WALL	FOOT	32	32						
XX001017	REMOVE RIGHT-OF-WAY MARKERS	EACH	14	2	12					
X0300230	FURNISH RIGHT-OF-WAY MARKERS, SPECIAL	EACH	33		33					
X0321461	PILLAR REMOVAL	EACH	2		2					
X0321690	BRICK WALL REMOVAL	FOOT	31	31						
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1901						1,901	
X0322924	RETAINING WALL REMOVAL	SQ FT	5,325		5,325					
X0322936	FLARED END SECTION REMOVE EXISTING	EACH	5	2	3					
X0323080	DRAINAGE SCUPPER, DS-12	EACH	5			3				2
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	90							90
X0751105	REMOVAL OF EXISTING CONCRETE DECK NO. 1	EACH	1							1
X0751205	REMOVAL OF EXISTING CONCRETE DECK NO. 2	EACH	1			1				
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	1783	869	914					
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	3982	2791	1,191					
X3550610	BITUMINOUS BASE COURSE SUPERPAVE 9 1/2"	SQ YD	8	8						
X3550815	BITUMINOUS BASE COURSE SUPERPAVE 11 3/4"	SQ YD	38,314	28,215	10,099					
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	15	12	3					
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	3	2					
X4023000	TEMPORARY ACCESS (ROAD)	EACH	12	9	3					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	7712	5927	1,785					
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	599		599					
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	1,136	905	231					
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	160		160					
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE N50	TON	227	131	96					
X4402815	ISLAND PAVEMENT REMOVAL AND REPLACEMENT	SQ FT	97		97					
<del>X5020501</del>	<del>UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 1</del>	<del>EACH</del>	<del>1</del>							
<del>X5020502</del>	<del>UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 2</del>	<del>EACH</del>	<del>1</del>							
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 3	EACH	1			1				
X5020504	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 4	EACH	1			1				
X6050700	REMOVE INLET BOX	EACH	6	2	4					
* X0324751	SOIL NAILED WALL	SQ FT	14,690							14,690
X0324752	STORM SEWER TO BE FILLED	CU YD	125.7		125.7					

© Y080

NOTE:  
RURAL STA. 942+50.00 TO STA. 1016+00.00  
URBAN STA. 1016+00.00 TO STA. 46+80.05  
\*DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SUMMARY OF QUANTITIES  
SHEET 6 OF 6

DRAWN BY ASB  
CHECKED BY SJK

Rev.

DATE 8/02