

SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	26RS-2	MARION	18	3
FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT NO.
CONTRACT NO. 94866				

CKT 10/28/04
 \94866\d02204pa.dgn
 SOO

SUMMARY OF QUANTITIES			BOI/FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		I000	SFTY-2A
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	257	257	
20300100	CHANNEL EXCAVATION	CU YD	305	305	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5	0.5	
20100100	STONE RIPRAP, CLASS A2	CS YD	87	87	
20100100	STONE RIPRAP, CLASS A4	CS YD	87	87	
20000100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	154	154	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30	30	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4281	4281	
40600300	AGGREGATE (PRIME COAT)	TON	80	80	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	267	267	
40600990	TEMPORARY RAMP	SQ YD	27	27	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	33984	33984	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	1400	1400	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	204	204	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	281	281	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	754	754	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	1890	1890	
48202315	BITUMINOUS SHOULDERS SUPERPAVE 5 3/4"	SO YD	8563	8563	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	4	4	
54248515	CONCRETE COLLAR	EACH	9	9	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1068.5	1068.5	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	0	0	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	

SUMMARY OF QUANTITIES			BOI/FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		I000	SFTY-2A
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7	7	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5136	5136	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28506	28506	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	428	428	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	28506	28506	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	161	161	
* 78200410	CHADBALL MARKERS, TYPE A	EACH	20	20	
* 78301000	TERMINAL MARKER - DIRECT APPLIED	EACH	0	0	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	3596	3591	5
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	1798	1793	5
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	61	61	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
 HORIZ. DATE

DRAWN BY
 CHECKED BY