

teos\eyck
4/4/2005
c:\projects\94866d\02204pa.dgn
PVS

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	26RS-2	MARION	/B	6
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 94866

PAVING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	EXCAVATING AND GRADING EXISTING SHOULDERS	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS SHOULDERS SUPERPAVE 5 3/4"	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT REMOVAL	BCSC, SUPERPAVE, MIX "C", N50	LEVEL BINDER (MACHINE METHOD), SUPERPAVE N50
	LIN FT	FEET	SQ YD	UNIT	GAL	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	FOOT	FOOT	SQ FT	FOOT	TON
708+13.00 TO 717+34.17	921.2	24	2456.5	18.4	307.1	6.1	133.3	13.3	2323.1	61	614	368	2072	31	258	129
STA. EQ 717+34.17 BK = 717+12.79 AH																
717+12.79 TO 820+40.90	10328.1	24	27541.6	206.6	3442.7	68.9			27541.6	591	6886	4132	22955	344	2892	1446
STA. EQ. 820+40.90 BK = 820+41.17 AH																
820+41.17 TO 836+36.00	1594.8	24	4252.8	31.8	531.6	10.6	133.3	13.3	4119.5	102	1063	636	3479	53	446	223
TOTAL QUANTITIES	12844.10		34251	257	4281	86	267	27	33984	754	8563	5136	28506	428	3596	1798

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**PAVEMENT
SCHEDULE**

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY