

teasleyck  
3/31/2005  
c:\projects\94905d\04201pa.dgn  
SQQ3

# SUMMARY OF QUANTITIES

FBI NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7)RS-1	JEFFERSON	48	7

CONTRACT NO. 94905

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000	X771-2A 041-0069	X771-2A 041-0080		
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	20343	20343				
X4409420	BITUMINOUS SURFACE REMOVAL 3 1/4"	SQ YD	160971	160971				
X6055701	CONCRETE MEDIAN, TYPE SM-4.06	SQ FT	513		513			
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	1			1		
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	2	2				
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	2136		1414	722		
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	2136		1414	722		
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1			1		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	8		2	6		
Z0017202	DOWEL BARS 1 1/2"	EACH	1204	1204				
Z0031300	JACKING AND CRIBBING	L SUM	1		0.7	0.3		
Z0075310	TIE BARS 3/4"	EACH	420	420				
Z0076600	TRAINEES	HOUR	1000	1000				
Z0077800	WOOD POST	EACH	66	66				

⊙  
\*

⊙ Y080  
\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
DATE: HORIZ.

DRAWN BY  
CHECKED BY