

teaslejack
3/31/2005
c:\projects\94905d\04201pa.dgn
PM

PAVEMENT MARKING SCHEDULE

FAI SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7)RS-1	JEFFERSON	48	14
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	
CONTRACT NO. 94905				

STATION TO STATION	LENGTH FEET	EOXY PAVEMENT MARKING - LINE 4" (YELLOW)	EOXY PAVEMENT MARKING - LINE 4" (WHITE)	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	EOXY PAVEMENT MARKING - LINE 8" (WHITE)	EOXY PAVEMENT MARKING - LINE 24" (WHITE)	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 4" (YELLOW)	TEMPORARY PAVEMENT MARKING - LINE 4" (WHITE)	TEMPORARY PAVEMENT MARKING - LINE 6" (WHITE)	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	DELINEATORS
		FEET	FEET	FEET	FEET	FEET	FEET	SO FT	FEET	FEET	FEET	FEET	FEET	EACH	EACH
I-64 EB															
2085+70.47 TO 2119+25.00	3354.53	3354.5	3354.5	838.6			1207.6	201.3	3354.5	3354.5	838.6			84	8
2119+25.00 TO 2122+15.00	290	290		72.5			81.2	13.5	290		72.5			7	
2122+15.00 TO 2126+38.58	423.58	423.6		105.9	423.6		118.6	19.8	423.6		105.9	423.6		21	
2126+38.58 TO 2149+83.96	2345.38	2345.4	2345.4	586.3		12.0	844.3	140.7	2345.4	2345.4	586.3		12.0	59	6
2149+83.96 TO 2160+65.00	1081.04	1081		270.3		12.0	302.7	50.4	1081		270.3		12.0	27	
2160+65.00 TO 2198+28.00	3763	3763	3763	940.8			1354.7	225.8	3763	3763	940.8			94	9
2198+28.00 TO 2199+92.00	Brdg Omission														
2199+92.00 TO 2362+11.77	16219.77	16219.8	16219.8	4054.9			5839.1	973.2	16219.8	16219.8	4054.9			405	41
I-64 WB															
2085+70.47 TO 2115+25.00	2954.53	2954.5	2954.5	738.6			1063.6	177.3	2954.5	2954.5	738.6			74	7
2115+25.00 TO 2126+11.82	1086.82	1086.8		271.7			304.3	50.7	1086.8		271.7			27	
2126+11.82 TO 2149+64.46	2352.64	2352.6	2352.6	588.2			847	141.2	2352.6	2352.6	588.2			59	6
2149+64.46 TO 2154+00.00	435.54	435.5		108.9	435.5		122	20.3	435.5		108.9	435.5		22	
2154+00.00 TO 2156+70.00	270	270		67.5			75.6	12.6	270		67.5			7	
2156+70.00 TO 2198+28.00	4158	4158	4158	1039.5			1496.9	249.5	4158	4158	1039.5			104	10
2198+28.00 TO 2199+92.00	Brdg Omission														
2199+92.00 TO 2362+11.77	16219.77	16219.8	16219.8	4054.9		24.0	5839.1	973.2	16219.8	16219.8	4054.9		24.0	405	41
RAMP A															
0+29.00 TO 1+15.00	86	86	86						86	86					2
1+15.00 TO 13+30.01	1215.01	1215	1215						1215	1215					24
13+30.01 TO 14+24.90	94.89	94.9			94.9				94.9			94.9			2
14+24.90 TO 14+64.75	39.85	39.8	10						39.8	10					1
14A+64.75=2125+71.97															
2125+71.97 TO 2122+72.00	299.97	300	75						300	75					3
2122+72.00 TO 2115+22.00	750	750							750						8
RAMP B															
14+22.00 TO 13+60.00	62	62	62						62	62					1
13+60.00 TO 13+20.00	40	40	40						40	40					1
13+20.00 TO 0+50.00	1270	1270	1270						1270	1270				15	25
0+50.00 TO 0+00.00	50	50			50				50			50		4	1
OB+00=2150+15.72															
2150+15.72 TO 2154+00.00	384.28	384.3	384.3		384.3				384.3			384.3		29	4
2154+00.00 TO 2156+70.00	270	270							270					14	3
RAMP C															
0+19.00 TO 0+98.00	79	79	79						79	79					2
0+98.00 TO 1+04.00	6	6	6						6	6					
1+04.00 TO 13+10.00	1206	1206	1206						1206	1206					24
13+10.00 TO 14+16.55	106.55	106.6			106.6				106.6			106.6			1
14+16.55 TO 14+56.40	39.85	39.9	10						39.9	10					
14C+56.40=2150+23.8															
2150+23.80 TO 2153+23.80	300	300	75						300	75					3
2153+23.80 TO 2160+65.00	741.2	741.2							741.2						7
RAMP D															
14+05.00 TO 13+40.00	65	65	65						65	65					1
13+40.00 TO 13+00.00	40	40	40						40	40					1
13+00.00 TO 0+50.00	1250	1250	1250						1250	1250				15	25
0+50.00 TO 0+00.00	50	50			50				50			50		4	1
0D+00=2125+87.37															
2125+87.37 TO 2122+15.00	372.37	372.4	372.4						372.4			372.4		28	4
2122+15.00 TO 2119+25.00	290	290							290					15	3
TOTALS		64063	56857	13739	1917	48	19497	3250	64063	56857	13739	1917	48	1519	275

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING SCHEDULE

SCALE: VERT. DATE
HORIZ. DRAWN BY
CHECKED BY