

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
750	(112,113) Y, WRS	FAYETTE	159	4
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 94927

SUMMARY OF QUANTITIES			80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE	ITEM	UNIT	TOTAL QUANTITIES	I000-2A	Y080
* 7800110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	79711	79711	
* 7810010	RAISED REFLECTIVE PAVEMENT MARKER	EACH	275	275	
* 7820040	GUARDRAIL MARKERS	EACH	21	21	
* 7820100	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8	
	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	275	275	
B200114	TREE (EASTERN REDBUD) 1 1/2" CALIPER, BALLED AND BURLAPPED	EACH	118	118	
B2010016	TREE (SHADBLow SERVICEBERRY) 2" CALIPER, BALLED AND BURLAPPED	EACH	118	118	
B2010165	TREE (KOUSSA DOGWOOD) 8' HEIGHT, BALLED AND BURLAPPED	EACH	118	118	
① 3007660	TRAINERS	HOUR	500	500	
X0322263	CULVERT DROP BOX	EACH	6	6	
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	2020	2020	
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	4	4	
X3550010	BITUMINOUS BASE COURSE SUPERPAVE	TON	313	313	
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9"	SQ YD	14671	14671	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C" N50	TON	4929	4929	
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL 19.0, N70	TON	480	480	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	TON	3286	3286	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	96	96	
X6013700	PIPE UNDERDRAIN REMOVAL (SPECIAL)	FOOT	1600	1600	
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	100	100	
Z0041500	PLUG EXISTING CULVERTS	EACH	2	2	

• DENOTES SPECIALTY ITEMS
 ① Y080

PLAN SURVEYED BY: _____ DATE: _____
 PLOTTED BY: _____
 NOTE BOOK NO. _____
 NO. _____
 PART OF WAY CHECKED BY: _____
 PAID FILE NAME: _____

PLAN SURVEYED BY: _____ DATE: _____
 PLOTTED BY: _____
 NOTE BOOK NO. _____
 NO. _____
 PART OF WAY CHECKED BY: _____
 PAID FILE NAME: _____

REVISIONS	
NAME	DATE
KdG	3/02/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 2 OF 2 SHEETS
 F.A.P. 750 (IL. RTE. 185)
 SECTION 112,113 - FAYETTE CO.
 SCALE: _____
 DATE: JANUARY 19, 2005
 DRAWN BY: CRO
 CHECKED BY: RCY

I:\2003\030045\0002\civil\phase 2 kdg\dgn\p2.schedule of quantities.750.dgn 2/25/03 PM 3/2/2005

Rev.