

teasleyck
 5/3/2005
 c:\projects\94962a\03102pa.dgn
 SOQ 2

SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
750	(114) Y. WRS	FAYETTE	74	4
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 94962

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000-2A	SFTY-2A
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	28	28	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	18	18	
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	11	11	
60602800	CONCRETE GUTTER, TYPE B	FOOT	378	378	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3793	3793	
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	59		59
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	13	13	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	17	17	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	90	90	
60621600	CONCRETE MEDIAN, TYPE SM	SQ FT	72	72	
66700095	PERMANENT SURVEY MARKERS	EACH	3	3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11	11	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	962	962	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3454	3454	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	404	404	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	113	113	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	30	30	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	107	107	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3454	3454	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	404	404	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	113	113	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30	30	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	81	81	

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000-2A	SFTY-2A
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	41	41	
* A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	6	6	
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	818	818	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	8	8	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1	
X4023000	TEMPORARY ACCESS (ROAD)	EACH	9	9	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	857	850	7
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	779	774	5
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	54	54	
XX002909	CLASS SI CONCRETE	CU YD	0.7	0.7	
Z0023900	FILLING EXISTING WELLS	EACH	1	1	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE