

ROUTE NO	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 856 C.H. 1	02-00041 -01-RS	MONROE	27	4

FEDERAL AID PROJECT
CONTRACT NO. 97248

SUMMARY OF QUANTITY			CONSTRUCTION TYPE CODE		TOTAL QUANTITY
CODE NO.	ITEM	UNIT	1000-2A REALIGNMENT FHWA-90% COUNTY-10%	1000 RESURFACING FHWA-80% COUNTY-20%	
* X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", NS0	TON	540.0	6893.0	7433.0
* X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, NS0	TON	430.0	562.0	992.0
* X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE NS0	TON	347.0	-	347.0
* XX004949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	17.2	174.5	191.7
20200100	EARTH EXCAVATION	CU. YD.	905.0	249.0	1154.0
20400800	FURNISHED EXCAVATION	CU. YD.	759.0	116.0	875.0
* 21400100	GRADING AND SHAPING DITCHES	FOOT	-	400.0	400.0
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.9	0.5	2.4
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150.0	50.0	200.0
28000300	TEMPORARY DITCH CHECKS	EACH	22.0	8.0	30.0
28000400	PERIMETER EROSION BARRIER	FOOT	600.0	-	600.0
28000500	INLET AND PIPE PROTECTION	EACH	5.0	1.0	6.0
30200650	PROCESSING MODIFIED SOILS 12"	SQ. YD.	2401.0	1245.0	3646.0
30201500	LIME	TON	58.0	30.0	88.0
31101300	SUB-BASE GRANULAR MATERIAL, TYPE B 5"	SQ. YD.	2401.0	-	2401.0
31101800	SUB-BASE GRANULAR MATERIAL, TYPE B 10"	SQ. YD.	452.0	-	452.0
35100700	AGGREGATE BASE COURSE, TYPE A B"	SQ. YD.	2866.7	-	2866.7
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	50.0	-	50.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1001.5	3230.0	4231.5
40600300	AGGREGATE (PRIME COAT)	TON	17.04	96.0	113.04
40600980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ. YD.	-	782.0	782.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ. YD.	-	454.0	454.0
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ. YD.	153.0	7922.0	8075.0
44000100	PAVEMENT REMOVAL	SQ. YD.	1972.0	-	1972.0
44000400	GUTTER REMOVAL	FOOT	-	216.0	216.0
* 44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ. YD.	-	221.0	221.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	820.0	1965.0	2785.0
* 48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ. YD.	-	178.0	178.0
* 50105220	PIPE CULVERT REMOVAL	FOOT	167.0	-	167.0
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	30.0	-	30.0
* 54215556	METAL END SECTIONS 21"	EACH	1.0	-	1.0
* 60101805	PIPE DRAINS 8" (SPECIAL)	FOOT	165.0	-	165.0
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	-	42.0	42.0

SUMMARY OF QUANTITY			CONSTRUCTION TYPE CODE		TOTAL QUANTITY
CODE NO.	ITEM	UNIT	1000-2A REALIGNMENT FHWA-90% COUNTY-10%	1000 RESURFACING FHWA-80% COUNTY-20%	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ. FT.	-	71.5	71.5
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	0.5	0.5	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	360.0	2484.0	2844.0
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ. FT.	-	62.4	62.4
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	6370.0	76637.0	83007.0
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	-	278.0	278.0
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	-	197.0	197.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	60.0	828.0	888.0
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	-	62.4	62.4
78000500	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	FOOT	-	278.0	278.0
78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	-	197.0	197.0
78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	6370.0	76637.0	83007.0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	-	86.0	86.0
78300505	PAINT PAVEMENT MARKING REMOVAL	FOOT	-	386.0	386.0

KASKASKIA RD.
SUMMARY OF QUANTITIES

SECTION 02-00041-01-RS

MONROE COUNTY, IL