

## DETOUR SIGNING DETAIL

LEGEND

•

DETOUR AHEAD SIGNS
DETOUR SIGNS W/ ARROWS

## SCHEDULE OF QUANTITIES FOR DETOUR TRAFFIC CONTROL AND MAINTENANCE

	71110 11712111 E1111110E								
	ITEH NUMBER	ITEM	UNIT	QUANTITY					
	40200800	AGGREGATE SURF, CSE. TYPE B	TON	1800					
	40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33					
	40300400	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	TON	208					
	40300600	SEAL COAT AGGREGATE	TON	2080					
	70101830	TRAFFIC CONT. & PROT. STD. BLR 21	L,SUM	1 .					
×	70102550	TRAF. CONT. & PROT. FOR TEMP. DETOUR	EACH	1					

\*See Special Provisions

## NOTES

- The Contractor shall maintain the roadway surface
  of the detour route throughout the duration of the
  contract as directed by the Engineer. This may include
  but is not limited to patching, aggregate surface/base
  repair and seal coating.
- The Contractor shall repair all damaged areas and seal coat all local detour routes upon completion of construction and closure of detour route.
- The contractor shall maintain all detour route signing as shown in the plans and specified in the special provisions.
- 4. The Aggregate Surface Course, Bituminous Materials (Prime Coat), Bituminous Materials (Cover and Seal Coats) and Seal Coat Aggregate quantities have been placed in the contract to repair and restore the temporary detour route during and after completion of construction of the bridge as directed by the Engineer.
- No additional compensation will be given for frequency of repairs needed as directed by the Engineer.

DETOUR ROUTE DETAILS, QUANTITIES AND REQUIREMENTS

 ROUTE	SECTION	COUNTY	TOTAL	SHEET NO.	Y.
FAS 738	01-00072-00-BR	GREENE	28	3	74.75
EEDERAL AT	n panient				1_

CONTRACT NO. 97249

ROLECT MANAGER DAVID N. MARTH Y

NGN. OF RECORD: DAVID N. MARTH P

REG. NC: 062-046888

RYYR OF RECORD: MIKE SCHNELTON #

HIGHWAY DEPARTMENT

ACCOUNT: BHHP BHIDGE
DATE: JANUARY 31, 2005
DATE: JANUARY 31, 2005
DESLOWED BY: DAVID M. MARTH
GRAWN BY: DAVID M. MARTH
GRAWN BY: DAVID M. MARTH

FAS 738 OVER

SECTION 01-00072-00-BR

DETOUR ROUTE DETAIL, CONSTRUCTION DETAILS AND QUANTITY SCHEDULES FAS 738 OVER HURRICANE CREEK

SECTION 01-00072-00-BR

**GREENE COUNTY** 

DRAWING

SHEET OF