F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9182	00-00186-05-RS	ST CLAIR	11	3
STA. 5+60.00		STA. 26+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97252

SUMMARY OF QUANTITIES

1000

CODED PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1506
40600300	AGGREGATE (PRIME COAT)	TON	31
40600990	TEMPORARY RAMP	SQ YD	125
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	90
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	14568
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	430
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	12
44200138	PAVEMENT PATCHING, TYPE IV, 11 INCH	SQ YD	480
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	9471
60255500	MANHOLES TO BE ADJUSTED	EACH	1
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	10
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	430
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3264
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1088
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4086
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	106
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	102
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	2109
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N70	TON	633

REVISIONS	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NO SCALE
DRAWN BY: DEG
DATE: 03/16/05
CHECKED BY: WEB

MAY 12, 2005 11:26:28 C:\projects\...