| F.A.P RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 869 | (103)I | SALINE | 64 | 21 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

CONTRACT NO. 98896

LT. STA. 1034+33.6
EXIST. 18" RCCP TO BE REMOVED
PIPE CULVERT REMOVAL
PIPE CULVERTS, CLASS A, TYPE 1 18"
PRECAST REINFORCED CONCRETE
FLARED END SECTIONS 18"

STA. 1037+72.1
EXIST. 4' x 3' CONCRETE BOX CULVERT
BOX CULVERT REMOVAL
PIPE CULVERTS, CLASS A, TYPE 1 54"
LT. 28', USFL = 405.18
RT. 28', DSFL = 404.90
PRECAST REINFORCED CONCRETE FLARED
END SECTIONS 54"

STONE RIPRAP, CLASS A4
FILTER FABRIC FOR USE WITH RIPRAP
LT. STA. 1039+58.4
SEE DETAIL, SHEET NO. 28

LT. STA. 1042+53.3
EXIST. 15" CMP TO BE REMOVED
PIPE CULVERTS, CLASS D, TYPE 1 15"
END SECTIONS 15"

CONSTRUCTION LIMITS

PROP. EXIST. PERMANENT EASEMENT R.O.W. LINE

STONE RIPRAP, CLASS A4
RT. STA. 1038+75 TO STA. 1039+58.4

℄ FAP 869 (IL 34)

STA. 1039+58.4
EXIST. 2' x 2' CONCRETE BOX CULVERT
EXTEND WITH
PIPE CULVERTS, CLASS A, TYPE 1 30"
LT. 19', USFL = 403.46
RT. 17', DSFL = 402.54
PRECAST REINFORCED CONCRETE FLARED
END SECTIONS 30" (RT. STA. 1039+58.4)
CONCRETE COLLAR
SEE DETAIL, SHEET NO. 29
CAST-IN-PLACE REINFORCED CONCRETE
END SECTION (LT. STA. 1039+58.4)

STONE RIPRAP, CLASS A4
RT. STA. 1039+58.4 TO STA. 1040+75

STONE RIPRAP, CLASS A4
FILTER FABRIC FOR USE WITH RIPRAP
RT. STA. 1039+58.4
SEE DETAIL, SHEET NO. 28

STA. 1045+10.3
EXIST. 4' x 4' CONCRETE BOX CULVERT
BOX CULVERT REMOVAL
PIPE CULVERTS, CLASS A, TYPE 1 54"
LT. 28', USFL = 407.00
RT. 28', DSFL = 406.95
PRECAST REINFORCED CONCRETE FLARED
END SECTIONS 54"

STONE RIPRAP, CLASS A4
FILTER FABRIC FOR USE WITH RIPRAP
RT. STA. 1045+10.3
SEE DETAIL, SHEET NO. 28

TREES SCRUB ROCK SIGN

50' 0 25' 50'

N

9

PROFILE
SURVEYED
PLOTTED
NOTE BOOK
NO.
DRAWN
CHECKED
STA. TIES
STRUCTURE NOTATIONS CHKD

PLAN
SURVEYED
PLOTTED
NOTE BOOK
NO.
DRAWN
CHECKED
ALIGNMENT
CADD FILE NAME

DATE BY

Friday January 21, 2005 @ 2:17:58 PM
c:\projects\d8392\d8392s2s2.dgn
c:\projects\d8392\d8392s2s2.dgn
34salinecty\projects\d8392\d8392s2s2.dgn

LV=2-29.24.45
LV=2-30.22.24-35.37-63

EXISTING ℄ PROFILE FAP 869 (IL 34)
PROPOSED ℄ PROFILE FAP 869 (IL 34)
STANDARD DITCH
PROPOSED LEFT DITCH
PROPOSED RIGHT DITCH
PLOTTED 10' LOWER FOR CLARITY
+00.00 EL. 412.70
400.00' V.C.
+00.00 EL. 413.72
200.00' V.C.
+05.00 EL. 414.98
VPI STA. 1042+00.00
ELEVATION 412.12

| STA. | 1032 | 1033 | 1034 | 1035 | 1036 | 1037 | 1038 | 1039 | 1040 | 1041 | 1042 | 1043 | 1044 | 1045 | 1046 | 1047 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| EXIST. | 414.68 | 414.49 | 414.25 | 414.12 | 413.62 | 412.58 | 411.29 | 410.29 | 409.71 | 409.35 | 409.25 | 408.90 | 408.77 | 408.62 | 408.50 | 408.26 |
| PROP. | 414.99 | 414.85 | 414.71 | 414.56 | 414.42 | 414.28 | 414.13 | 413.99 | 413.84 | 413.70 | 413.56 | 413.41 | 413.27 | 413.13 | 412.98 | 412.84 |
| STA. | 408.14 | 408.29 | 408.42 | 408.46 | 408.53 | 408.88 | 409.20 | 409.63 | 410.45 | 411.71 | 413.17 | 414.21 | 414.98 | 415.55 | | |
| EXIST. | 412.70 | 412.55 | 412.57 | 412.66 | 412.83 | 413.06 | 413.35 | 413.72 | 414.12 | 414.51 | 414.91 | 415.31 | 415.71 | 416.11 | | |

**PLAN PROFILE SHEET STA. 1032+00 TO STA. 1047+00**