

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P. 782	-	GALLATIN	7	3

FED. ROAD DIST. NO. 7 ILLINOIS PROJECT  
\*FY 05 BEAM REPLACEMENT

CONSTRUCTION TYPE CODE: SFTY-2A		100% STATE	
CODE NO.	ITEM DESCRIPTION	UNIT	QUANTITY
42001300	PROTECTIVE COAT	SQ YD	20.7
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	5.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.9
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	316
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	29.2
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	105
67100100	MOBILIZATION	L. SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	14
70400100	TEMPORARY CONCRETE BARRIER	FOOT	270
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	147
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	316
X0324427	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	107
X4066418	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90	TON	5.3
X7015000	CHANGEABLE MESSAGE SIGN	CAL. MO.	1
XX002024	ENGINEER'S FIELD OFFICE	CAL MO	2
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	2
△ Z0030450	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

△ SFTY-3N \* SPECIALTY ITEMS