

SUMMARY OF QUANTITIES


**RO010
TOTAL SHEETS ■ 24**

REVISIONS		
NUMBER	BY	DATE


0 1
THIS BAR IS EQUAL TO 1"
AT FULL SCALE (17 X 11).

SEQ NO	ITEM NO	DESCRIPTION	UNIT	REHABILITATE NORTH LOT EST. QUANTITY	EXPAND WEST LOT EST. QUANTITY	TOTAL EST. QUANTITY	RECORD TOTAL QUANTITY
1	AR106511	TYPE A AREA LIGHT POLE W/1 FIXTURE	EACH	5.00	0.00	5.00	
2	AR106513	TYPE A AREA LIGHT POLE W/3 FIXTURES	EACH	6.00	0.00	6.00	
3	AR106514	TYPE A AREA LIGHT POLE W/4 FIXTURES	EACH	6.00	2.00	8.00	
4	AR106905	REMOVE LIGHT POLE & FIXTURE	EACH	15.00	0.00	15.00	
5	AR108084	1/C #4 XLP-USE	L.F.	5,840.00	820.00	6,660.00	
6	AR108758	1/C #8 GROUND	L.F.	1,760.00	410.00	2,170.00	
7	AR109620	LIGHTING CONTROL SYSTEM	L.S.	1.00	0.00	1.00	
8	AR110212	2" STEEL DUCT, DIRECT BURY	L.F.	1,630.00	365.00	1,995.00	
9	AR110214	4" STEEL DUCT, DIRECT BURY	L.F.	90.00	0.00	90.00	
10	AR110610	ELECTRICAL HANDHOLE	EACH	6.00	0.00	6.00	
11	AR151420	CLEARING TREES 0-2.5' BUTT. DIA.	EACH	8.00	0.00	8.00	
12	AR152410	UNCLASSIFIED EXCAVATION	C.Y.	0.00	1,840.00	1,840.00	
13	AR152540	SOIL STABILIZATION FABRIC	S.Y.	14,060.00	4,140.00	18,200.00	
14	AR162408	CLASS E FENCE, VINYL-8'	L.F.	1,220.00	0.00	1,220.00	
15	AR162620	CLASS E GATE-20'	EACH	3.00	0.00	3.00	
16	AR163910	FENCE REMOVAL, WOOD	L.F.	1,115.00	0.00	1,115.00	
17	AR208515	POROUS GRANULAR EMBANKMENT	C.Y.	2,425.00	200.00	2,625.00	
18	AR209608	CRUSHED AGG. BASE COURSE - 8"	S.Y.	14,060.00	4,140.00	18,200.00	
19	AR401610	BITUMINOUS SURFACE COURSE	TON	3,515.00	980.00	4,495.00	
20	AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1.00	1.00	2.00	
21	AR501604	4" PCC SIDEWALK	S.F.	0.00	1,470.00	1,470.00	
22	AR602510	BITUMINOUS PRIME COAT	GAL.	4,450.00	1,240.00	5,690.00	
23	AR603510	BITUMINOUS TACK COAT	GAL.	1,113.00	310.00	1,423.00	
24	AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	3,430.00	800.00	4,230.00	
25	AR701518	18" RCP, CLASS IV	L.F.	690.00	0.00	690.00	
26	AR751560	MANHOLE 6'	EACH	8.00	0.00	8.00	
27	AR751927	REPLACE FRAME & GRATE	EACH	0.00	2.00	2.00	
28	AR754410	COMB. CONCRETE CURB & GUTTER	L.F.	1,585.00	740.00	2,325.00	
29	AR754904	REMOVE COMB CURB & GUTTER	L.F.	0.00	60.00	60.00	
30	AR800859	CROSSWALK LIGHTING SYSTEM	L.S.	1.00	0.00	1.00	
31	AR800860	WALKWAY LIGHTING	L.S.	1.00	0.00	1.00	
32	AR800861	BIT. PAVMENT PULVERIZATION	S.Y.	15,470.00	0.00	15,470.00	
33	AR800868	SOIL GUARD	S.Y.	4,840.00	480.00	5,320.00	
34	AR901510	SEEDING	ACRE	1.00	0.10	1.10	
35	AR904510	SODDING	S.Y.	416.00	0.00	416.00	
36	AR905520	TOPSOILING (FROM OFF SITE)	C.Y.	200.00	0.00	200.00	
37							
38							
39							
40							


**GREATER ROCKFORD AIRPORT AUTHORITY
ROCKFORD, ILLINOIS
ILLINOIS PROJECT: RFD-2820
NORTH AND WEST AUTO PARKING
SUMMARY OF QUANTITIES**



CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS



Northwest
Chicago
International
Airport

DESIGN BY: TAS
 DRAWN BY: CMT
 CHECKED BY: TAS
 APPROVED BY: 
 DATE: 5.13.005
 JOB No: 05258-04-00