

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES	ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
BASE BID					ALTERNATE 'A'				
AR107408	L-806 WIND CONE-8' LIGHTED	EA.	2		AS152410	UNCLASSIFIED EXCAVATION	C.Y.	73,026	
AR107900	REMOVE WIND CONE	EA.	1		AS209510	CRUSHED AGGREGATE BASE COURSE	TON	7,200	
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	15,408		AS501505	5" PCC PAVEMENT	S.Y.	29,563	
AR108656	3/C #6 600 V UG CABLE IN UD	L.F.	31,150		AS501530	PCC TEST BATCH	EACH	1	
AR109100	CONSTRUCT ELECTRICAL VAULT	L.S.	1		ALTERNATE 'B'				
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1		AT152410	UNCLASSIFIED EXCAVATION	C.Y.	73,391	
AR109901	REMOVE ELECTRICAL VAULT	L.S.	1		AT201610	BITUMINOUS BASE COURSE	TON	4,491	
AR110014	4" DIRECTIONAL BORE	L.F.	1,142		AT201630	BITUMINOUS BASE TEST SECTION	EACH	1	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	41		AT209510	CRUSHED AGGREGATE BASE COURSE	TON	10,588	
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	72		AT401610	BITUMINOUS SURFACE COURSE	TON	2,661	
AR110610	ELECTRICAL HANDHOLE	EA.	2		AT401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR125410	MITL-STAKE MOUNTED	EA.	57		AT602510	BITUMINOUS PRIME COAT	GAL.	10,741	
AR125415	MITL-BASE MOUNTED	EA.	5		AT603510	BITUMINOUS TACK COAT	GAL.	1,497	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EA.	2						
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EA.	2						
AR125505	MIRL, STAKE MOUNTED	EA.	26						
AR125510	MIRL, BASE MOUNTED	EA.	9						
AR125540	MI THRESHOLD LIGHT STAKE MTD	EA.	14						
AR125610	REILS	PAIR	2						
AR125630	PLASI	EA.	2						
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1						
AR150540	HAUL ROUTE	L.S.	1						
AR151450	CLEARING AND GRUBBING	AC.	13						
AR152610	BUILDING DEMOLITION	L.S.	1						
AR155540	BY-PRODUCT LIME	TON	1,173						
AR155616	SOIL PROCESSING-16"	S.Y.	31,277						
AR156510	SILT FENCE	L.F.	2,750						
AR156511	DITCH CHECK	EA.	23						
AR156512	BALES	EA.	40						
AR156520	INLET PROTECTION	EA.	2						
AR156530	TEMPORARY SEEDING	AC	23						
AR156531	EROSION CONTROL BLANKET	S.Y.	12,328						
AR156540	RIPRAP	S.Y.	238						
AR161510	CLASS C FENCE	L.F.	10,497						
AR161624	CLASS C GATE-24'	EA.	2						
AR162504	CLASS E FENCE 4'	L.F.	1,042						
AR162605	CLASS E GATE-5'	EA.	2						
AR162624	CLASS E GATE-24'	EA.	1						
AR162900	REMOVE CLASS E FENCE	L.F.	203						
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	13,582						
AR620525	BLACK BORDER	S.F.	5,711						
AR701515	15" RCP CLASS IV	L.F.	120						
AR701518	18" RCP CLASS IV	L.F.	228						
AR701536	36" RCP CLASS IV	L.F.	160						
AR705526	6" PERFORATED UNDERDRAIN W/ SOCK	L.F.	10,091						
AR705546	6" NON PERFORATED UNDERDRAIN	L.F.	500						
AR705548	8" NON PERFORATED UNDERDRAIN	L.F.	500						
AR705550	10" NON PERFORATED UNDERDRAIN	L.F.	500						
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	25						
AR751410	INLET	EACH	2						
AR752415	PRECAST REINFORCED CONC. FES 15"	EACH	2						
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH	4						
AR752636	CONCRETE HEADWALL 36"	EACH	2						
AR800152	EXPLORATORY TRENCH	L.F.	3,700						
AR800429	FIELD TILE TRACING	EACH	10						
AR800575	WEED CONTROL LIGHT RING	EACH	111						
AR800576	INSTALL GROUND ROD	EACH	5						
AR800578	LIME AND FERTILIZE	AC.	6						
AR901510	SEEDING	AC.	45						
AR908510	MULCHING	AC.	45						

BY	
REVISION	
DATE	

TAYLORVILLE MUNICIPAL AIRPORT
TAYLORVILLE, ILLINOIS

I.L. PROJ.: TAZ-3166 A.I.P. PROJ.: 3-17-0100-87

FILE PROJECT NO. 828-03RWGD_0800	DATE 02/05/04
FILE PROJECT R-002FLP.DWG	
FILE PROJECT NTS	
FILE PROJECT DATE 02/05/04	
LAYOUT RAW 02/18/05	
DRAWN BAK 02/18/05	
REVIEWED CAH 03/28/05	



CONSTRUCT RUNWAY 9-27

SUMMARY OF QUANTITIES