



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 16, 2026

SUBJECT FAU Route 1273(Dundee Rd.)
Project STP-9J5V(819)
Section 2019-122-RS&SW
Cook County
Contract No. 62J64
Item No. 1, July 31, 2026, Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page iii of the Table of Contents to the Special Provisions
3. Added pages 209 & 210 to the Special Provisions
4. Revised Sheets 1, 2 & 3 of the Plans
5. Added sheet 14A to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

CONSTRUCTION REQUIREMENTS	150
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	159
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	160
COMPENSABLE DELAY COSTS (BDE)	177
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	181
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)	183
PAVEMENT MARKING (BDE)	184
PAVEMENT PATCHING (BDE)	184
PERFORMANCE GRADED ASPHALT BINDER (BDE)	185
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	190
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	190
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)	192
SIGN PANELS AND APPURTENANCES (BDE)	195
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	197
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	198
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	199
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	199
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	200
SURVEYING SERVICES (BDE)	201
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	202
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	202
WORK ZONE WIDTH RESTRICTION (BDE)	204
WORKING DAYS (BDE)	204
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	205
WEEKLY DBE TRUCKING REPORTS (BDE)	208
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	209

Revised 7/16/2026

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

IL 68 (Dundee Road) from I-94 (Edens Expressway) to Forest Way Drive, Glencoe, Cook County

- All excavation planned for ADA sidewalk improvements along both sides of IL 68 (Dundee Road) from I-94 (Edens Expressway) to Forest Way Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 68 (Dundee Road) and IL 43 (Waukegan Road), Northbrook, Cook County

- All excavation planned for ADA sidewalk improvements at all four quadrants of the Intersection of IL 68 (Dundee Road) and IL 43 (Waukegan Road). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

IL 68 (Dundee Road) W/o Pebblewood Lane, Northbrook, Cook County

- Station 41+80 to Station 43+20 (CL IL 68), 0 to 25 feet LT. All excavation planned for drainage improvements and repair of roadway sinkhole. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None