

MODEL: SOQ-1 [Sheet]
FILE NAME: c:\pwwork\widc\illinois.gov_merlin.jose@illinois.gov\d0936699\102324-sh1-SOQ.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	SIGNAL				
					80% FED 20% STATE	80% FED 20% STATE				
	Code No.	Item	Unit	Total Quantity	0005	0021				
	20200100	EARTH EXCAVATION	CU YD	13	13					
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	65	65					
	25200110	SODDING, SALT TOLERANT	SQ YD	65	65					
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	5783	5783					
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	5116	5116					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	81	81					
	40602985	HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70	TON	960	960					
	40605026	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, MIX "F", N80	TON	840	840					
	42001300	PROTECTIVE COAT	SQ YD	44	44					
	44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	8567	8567					
	44201003	CLASS B PATCHES, TYPE I, 13 INCH	SQ YD	25	25					
	44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	199	199					
	44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	273	273					
	44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	495	495					
	44201299	DOWEL BARS 1 1/2"	EACH	608	608					
	44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	10	10					
	44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	95	95					
	44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	94	94					
	44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	518	518					
	44213198	TIE BARS 1/2"	EACH	528	528					
	44213200	SAW CUTS	FOOT	5000	5000					

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	SIGNAL				
					80% FED 20% STATE	80% FED 20% STATE				
	Code No.	Item	Unit	Total Quantity	0005	0021				
	45100100	CRACK ROUTING (PAVEMENT)	FOOT	99809	99809					
	45100200	CRACK FILLING	POUND	28515	28515					
	45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	21082	21082					
	45200300	JOINT OR CRACK FILLING	POUND	6023	6023					
	60260100	INLETS TO BE ADJUSTED	EACH	9	9					
	60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1					
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1					
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	13	13					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1					
*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1					
*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1					
*	66901006	REGULATED SUBSTANCES MONITORING	CAL DA	4	4					
	67100100	MOBILIZATION	L SUM	1	1					
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
	70102637	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	EACH	1	1					
	70107006	PAVEMENT MARKING BLACKOUT TAPE, 6"	FOOT	802	802					
	70107025	CHANGEABLE MESSAGE SIGN	CAL DA	6	6					
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	10197	10197					
	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	850	850					
	70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	376	376					