

SUMMARY OF QUANTITIES - CONT

COUNTY:	UNION COUNTY
ROUTE:	FAP 885 / IL 146
FUNDING:	80% FEDERAL 20% STATE
LOCATION:	RURAL
TOTAL QUANTITY	ROADWAY
	0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28
70300100	SHORT TERM PAVEMENT MARKING	FOOT	8412	8412
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	2804	2804
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	122.4	122.4
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	70144	70144
70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	101	101
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4	122.4
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	70144	70144
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	70144	70144
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	101	101
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	355	355
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	355	355
78300201	PAVEMENT MARKER REMOVAL - GRINDING	SQ FT	2725	2725
X4430200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	54180	54180
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

△ REVISED 7-15-2026

MODEL: SQQ_3 [Sheet]
FILE NAME: c:\p\work\pilot\michaela.montgomery\1181389\0978B60-ShtC-SQQ.dgn

	USER NAME = Michaela.Montgomery	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					885	104RS-8	Union	18	8
		CHECKED -	REVISED -					CONTRACT NO. 78B60				
	PLOT DATE = 4/23/2026	DATE -	REVISED -		SCALE:	SHEET 3	OF 3 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE

PAVEMENT MARKING SCHEDULE													
LOCATION			LENGTH	PAINT PAVEMENT MARKING				THERMOPLASTIC PAVEMENT MARKING		RRPM	RRPM REM	COMMENTS	
STA TO STA				LINE - 4" WHITE	LINE - 4" YELLOW			LINE-24" WHITE	LETTERS & SYMBOLS				
					SOLID	SOLID LT	SOLID RT						SKIP - DASH
FAP 885/ IL 146			FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH			
438+27.50	TO	437+77.50	50.00	100			12.5	29		1	1	INTERSECTION	
437+77.50	TO	437+27.50	50.00	100			12.5			1	1		
437+27.50	TO	434+33.10	294.40	588.8	264		73.6			4	4		
434+33.10	TO	434+08.60						72	122.4			RAILROAD	
434+08.60	TO	377+60.00	5648.60	11297.2		581	1412.2			71	71		
377+60.00	TO	376+92.00	68.00	136			17.0			1	1	BRIDGE	
376+92.00	TO	293+54.40	8337.60	16675.2	1531.2	2376	2084.4			105	105		
293+54.54 AH	=	294+85.8 BK										STATION EQUATION	
294+85.80	TO	271+00.00	2385.80	4771.6			596.5			30	30		
271+00.00	TO	266+00.00	500.00	1000			125.0			7	7		
266+00.00	TO	265+34.00	66.00	132			16.5			1	1	BRIDGE	
265+34 AH	=	265+27.6 BK										STATION EQUATION	
265+27.60	TO	163+01.20	10226.40	20452.8	748	748	2556.6			128	128		
163+01.2 AH	=	185+28 BK										STATION EQUATION	
185+28.00	TO	181+15.00	413.00	826	403	403	103.3			6	6		
Total:				56079.6	2946.2	4108	7010.0	101	122.4	355	355		
				70144									

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION			LENGTH	TEMPORARY PAVEMENT MARKING - PAINT						PAVEMENT MARKING REM (GRINDING)	SHORT TERM PAVEMENT MARKING	SHORT TERM REMOVAL	COMMENTS INTERSECTION
STA TO STA				LINE - 4" WHITE	LINE - 4" YELLOW			LINE- 24" WHITE	LETTERS & SYMBOLS				
				SOLID	SOLID LT	SOLID RT	SKIP - DASH						
FAP 885/ IL 146			FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	FOOT	SQ FT		
438+27.50	TO	437+77.50	50.00	100			12.5		5.2	15.0	5.0		
437+77.50	TO	437+27.50	50.00	100			12.5		4.2	15.0	5.0		
437+27.50	TO	434+33.10	294.40	588.8	264		73.6		34.3	88.3	29.4		
434+33.10	TO	434+08.60						72	125.1				
434+08.60	TO	377+60.00	5648.60	11297.2		581	1412.2		492.2	1694.6	564.9		
377+60.00	TO	376+92.00	68.00	136			17.0		5.7	20.4	6.8		
376+92.00	TO	293+54.40	8337.60	16675.2	1531.2	2376	2084.4		839.5	2501.3	833.8		
293+54.54 AH	=	294+85.8 BK											
294+85.80	TO	271+00.00	2385.80	4771.6			596.5		198.8	715.7	238.6		
271+00.00	TO	266+00.00	500.00	1000			125.0		41.7	150.0	50.0		
266+00.00	TO	265+34.00	66.00	132			16.5		5.5	19.8	6.6		
265+34 AH	=	265+27.6 BK											
265+27.60	TO	163+01.20	10226.40	20452.8	748	748	2556.6		907.6	3067.9	1022.6		
163+01.2 AH	=	185+28 BK											
185+28.00	TO	181+15.00	413.00	826	403	403	103.3		64.3	123.9	41.3		
Total:				56079.6	2946.2	4108	7010.0	101	122.4	2725	8412	2804	
				70144									

REVISED 7-15-2026

MODEL: PVT MKGS [Sheet]
FILE NAME: c:\pvt_work\pvtolland\1181380\D978B60-SHE-Schedules.dgn