

1

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003	ROADWAY 0003	TRAFFIC SIGNALS 0021	STREET LIGHTING 0021	TRAFFIC SIGNALS 0021
					70% FED 30% STATE	100% VILLAGE	70% FED 30% VILLAGE	70% FED 30% VILLAGE	100% VILLAGE
					URBAN	URBAN	URBAN	URBAN	URBAN
+	81400300	DOUBLE HANDHOLE	EACH	2			2		
+	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1,350				1,350	
+	81800240	AERIAL CABLE, 2-1/C NO. 8 WITH MESSENGER WIRE	FOOT	300				300	
+	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	2				2	
+	84200804	REMOVAL OF POLE FOUNDATION	EACH	2				2	
+	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1		
+	85100500	PAINT NEW TRAFFIC SIGNAL POST	EACH	4					4
+	85100600	PAINT NEW MAST ARM AND POLE, UNDER 40 FOOT	EACH	1					1
+	85100800	PAINT NEW COMBINATION MAST ARM AND POLE, UNDER 40 FOOT	EACH	1					1
+	85100701	PAINT NEW MAST ARM AND POLE, 40 FOOT AND OVER	EACH	3					3
+	85100901	PAINT NEW COMBINATION MAST ARM AND POLE, 40 FOOT AND OVER	EACH	3					3
+	87301115	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 2C	FOOT	1,107			1,107		
+	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,107			1,107		
+	87301125	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 3C	FOOT	1,445			1,445		
+	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,445			1,445		
+	87301145	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 5C	FOOT	1,108			1,108		
+	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,108			1,108		
+	87301155	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 7C	FOOT	1,790			1,790		
+	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,790			1,790		
+	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	112			112		
+	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	506			506		

+ INDICATES SPECIALTY ITEM
* INDICATES CONSTRUCTION CODE 0042

MODEL Default
FILE NAME: S:\011600-1609\1610\028\Drawings\CAD\Misc-SSA\CAD_Sheets\1610058-ht-500.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = alexam	DESIGNED - MAG	REVISED - 09/02/2026
	DRAWN - DJW	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 9/2/2026	DATE - 2/27/2026	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 10 OF 17 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3561	08-00103-00-FP	COOK	254	14
CONTRACT NO. 61M29				
ILLINOIS FED. AID PROJECT				