



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 2, 2026

SUBJECT: FAS Route 368 (BUS 24)
Project HSIP-GRDI(268)
Section (35)N-2
Tazewell County
Contract No. 68H60
Item No. 49, September 18, 2026 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised the Table of Contents to the Special Provisions.
3. Revised pages 11-12 of the Special Provisions.
4. Revised sheets 6 and 23 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
CONSTRUCTION LAYOUT RESPONSIBILITY	2
UTILITIES – LOCATIONS/INFORMATION ON PLANS	2
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES	2
EMBANKMENT (RESTRICTIONS).....	3
SEEDING, MINOR AREAS	4
MOWING	4
PROOF ROLLING	5
SUBGRADE TREATMENT	5
HOT-MIX ASPHALT – TACK COAT (SPECIAL) OPTIONS	5
BACKFILL - PIPE CULVERTS	6
TRAFFIC CONTROL PLAN	6
WIDTH RESTRICTION SIGNING	7
PCC QMP ELECTRONIC REPORT SUBMITTALS	10
PCC AUTOMATIC BATCHING EQUIPMENT	10
POTHOLING FOR LOCATION OF EXISTING UNDERGROUND UTILITIES	10
TRAFFIC SIGNAL BACKPLATE	10
LUMINAIRE MAST ARM ASSEMBLIES (INCIDENTAL TO LUMINAIRE).....	12
MODIFICATION TO LIGHTING CONTROLLER FOR FLASHING BEACON OPERATION.....	13
CONDUIT CROSSING UNDER PAVEMENT	13
SHARED SIGNAL AND LIGHTING UNIT DUCT INSTALLATION.....	14
STEEL MAST ARM POLE WITH LUMINAIRES AND FLASHING BEACON	14
FLASHING BEACON SIGNAL HEAD OPERATION	15
GROUNDING FOR LIGHTING AND SIGNAL EQUIPMENT	15
CONDUIT SEALING	15
TESTING AND ENERGIZATION	16
SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE).....	16
SOLAR-POWERED FLASHING BEACON ASSEMBLY (DUAL-ALTERNATING).....	18
TRAFFIC CONTROL (SPECIAL)	19
WORKING RESTRICTIONS	20

AGGREGATE SUBGRADE IMPROVEMENT (BDE).....	20
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	22
COMPENSABLE DELAY COSTS (BDE)	38
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	41
EROSION CONTROL BLANKET (BDE)	44
HOT-MIX ASPHALT (BDE).....	46
PAVEMENT MARKING (BDE)	50
PAVEMENT PATCHING (BDE)	50
PERFORMANCE GRADED ASPHALT BINDER (BDE).....	51
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	56
SEEDING (BDE).....	58
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	63
SIGN PANELS AND APPURTENANCES (BDE).....	66
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	67
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	68
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	69
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	69
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	69
SURFACE TESTING OF PAVEMENTS – IRI (BDE).....	71
SURVEYING SERVICES (BDE)	77
TEMPORARY RUMBLE STRIPS (BDE)	77
TRAFFIC SIGNAL BACKPLATE (BDE)	78
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	78
WEEKLY DBE TRUCKING REPORTS (BDE).....	78
WOOD SIGN SUPPORT (BDE).....	79
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	79
WORK ZONE WIDTH RESTRICTION (BDE).....	81
WORKING DAYS (BDE).....	81

Backplates that are installed on existing signals shall be split backplates that are designed for installation on existing traffic signal heads. The individual halves on the backplate shall be secured with stainless steel washers, bolts, and locknuts to prevent the sections from separating. The use of metal clips is not allowed.

Basis of Payment: This work will be paid for at the contract unit price Each for TRAFFIC SIGNAL BACKPLATE and shall be payment in full for all labor, materials, and equipment required to furnish and install a traffic signal backplate with reflective tape as described above, complete.

The remainder of this page left blank intentionally.

Revised September 2, 2026

LUMINAIRE MAST ARM ASSEMBLIES (INCIDENTAL TO LUMINAIRE)

Description: This work shall consist of furnishing and installing luminaire mast arm assemblies for the roadway luminaires mounted on the steel mast arm pole assembly as shown on the plans and as directed by the Engineer. The luminaire installation shall include mounting hardware, mast arms, wiring, and all incidental materials required for a complete and operational lighting system.

The luminaires shall comply with the requirements of Section 821 of the Illinois Department of Transportation Standard Specifications. Luminaires shall be LED roadway type with output designation as shown in the plans.

Construction Requirements: The Contractor shall provide two (2) 10-foot steel truss-type luminaire mast arm assemblies for installation of luminaires. Orientation of mast arms and luminaires shall be as indicated on the plans.

Mast arms shall be structurally adequate for the application and shall conform to Section 1069 of the Illinois Department of Transportation Standard Specifications. All mounting hardware, fittings, pole attachments, and appurtenances required for a complete installation shall be provided.

The luminaire shall be installed in accordance with manufacturer recommendations and IDOT District 4 practices.

Revised September 2, 2026