

MODEL: Detail
FILE NAME: W:\p\p\ch1\kimm\self\grhane\05005595-IL_DOT_District_00595-001-2010-IL_127_river\Hartline_Creek_Pk1_Alexander_Co\CAUD\CAUD_Sheet\0778989-01-001.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				BRIDGE	BRIDGE
				0010	0010
				RURAL	S.N. 002-0039
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25	
20200100	EARTH EXCAVATION	CU YD	503	503	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	55	55	
20300100	CHANNEL EXCAVATION	CU YD	1545	1545	
20400800	FURNISHED EXCAVATION	CU YD	834	834	
25000320	SEEDING, CLASS 5	ACRE	0.75	0.75	
25000350	SEEDING, CLASS 7	ACRE	0.75	0.75	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	70	70	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	70	70	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	70	70	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.5	1.5	
25100115	MULCH, METHOD 2	ACRE	1.5	1.5	
25100630	EROSION CONTROL BLANKET	SQ YD	1502	1502	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75	75	

1

1 REVISED 8-31-2026

REV - MS



DESIGNED -	CPK	REVISED -	
DRAWN -	DMS	REVISED -	
CHECKED -	CPK	REVISED -	
DATE -	01-26-2026	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 7 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1907	17B-4	ALEXANDER	82	4
CONTRACT NO. 78989				
ILLINOIS FED. AID PROJECT				

MODEL: D:\sht
FILE NAME: W:\p\41\kdm\wells\phase0\05005954_DOT_Distd\1_00595400-4010-IL_127_0ver_Hullins_Creek_Ph1_Alexander_Co\CADD\CADD Sheets\0778989\se\technical\41.dgn

PERMANENT SEEDING							
LOCATION	SEEDING	NITROGEN	PHOSPHORUS	POTASSIUM	AGRICULTURAL	EROSION	MULCH
	CLASS 5	FERTILIZER	FERTILIZER	FERTILIZER	GROUND	CONTROL	METHOD 2
	ACRE	NUTRIENT	NUTRIENT	NUTRIENT	LIMESTONE	BLANKET	
		POUND	POUND	POUND	TON	SQ YD	ACRE
STA. 566+30.00 TO STA. 568+75.00 LT.	0.19	18	18	18	0.38		0.38
STA. 568+75.00 TO STA. 569+00.61 LT.	0.06	6	6	6	0.12	291	0.12
STA. 570+81.96 TO STA. 571+00.00 LT.	0.01	1	1	1	0.02	49	0.02
STA. 571+00.00 TO STA. 573+40.00 LT.	0.09	9	9	9	0.18		0.18
STA. 566+30.00 TO STA. 567+25.00 RT.	0.03	3	3	3	0.06		0.06
STA. 566+30.00 TO STA. 568+78.88 RT.	0.09	9	9	9	0.18	436	0.18
STA. 569+95.99 TO STA. 571+58.34 RT.	0.15	14	14	14	0.30	726	0.30
STA. 571+58.34 TO STA. 573+40.00 RT.	0.11	10	10	10	0.22		0.22
SUB-TOTAL	0.73	70	70	70	1.46	1502	1.46
TOTAL	0.75	70	70	70	1.50	1502	1.50

1

TEMPORARY EROSION CONTROL ITEMS			
LOCATION	SEEDING	TEMPORARY EROSION	PERIMETER
	CLASS 7	CONTROL SEEDING	EROSION BARRIER
	ACRE	POUND	FOOT
STA. 566+30.00 TO STA. 568+75.00 LT.	0.19	19	739
STA. 568+75.00 TO STA. 569+60.61 LT.	0.06	6	
STA. 570+81.96 TO STA. 571+00.00 LT.	0.01	1	322
STA. 571+00.00 TO STA. 573+40.00 LT.	0.09	9	
STA. 566+30.00 TO STA. 567+25.00 RT.	0.03	3	345
STA. 566+30.00 TO STA. 568+78.88 RT.	0.09	9	
STA. 569+95.99 TO STA. 571+58.34 RT.	0.15	15	484
STA. 571+58.34 TO STA. 573+40.00 RT.	0.11	11	
SUB-TOTAL	0.73	73	1890
TOTAL	0.75	75	1890

SHOULDERS			
LOCATION	HOT-MIX ASPHALT	HOT-MIX ASPHALT	PCC
	SHOULDERS 8"	SHOULDERS 10"	SHOULDERS 10"
	SQ. YD.	SQ. YD.	SQ. YD.
STA. 567+65 TO STA. 569+28.70 LT.	60		
STA. 570+57.52 TO STA. 573+18 LT.	84		
STA. 566+30 TO STA. 569+32.4 LT.			101
STA. 570+50.9 TO STA. 573+40 LT.			97
STA. 566+30 TO STA. 569+00.94 RT.		88	
STA. 570+29.76 TO STA. 571+06.8 RT.		70	
STA. 572+85.3 TO STA. 573+40 RT.		16	
TOTAL	144	174	198

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	RAISED REFLECTIVE
	PAVEMENT
	MARKER REMOVAI
	EACH
STA. 565+13 TO STA. 573+78	11
TOTAL	11

1 REVISED 8-31-2026



DESIGNED -	CPK	REVISED -	
DRAWN -	DMS	REVISED -	
CHECKED -	CPK	REVISED -	
DATE -	01-26-2026	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 4 OF 4 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1907	17B-4	ALEXANDER	82	18
CONTRACT NO. 78989				
ILLINOIS FED. AID PROJECT				