

MODEL: Signature [Sheet]
FILE NAME: c:\pwworking\midia\knapand1227961\0878C34_SHA_Cover.dgn

USER NAME	elise.knop	DESIGNED	-	REVISED	-
		DRAWN	-	REVISED	-
		CHECKED	-	REVISED	-
PLOT DATE	5/12/2026	DATE	-	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNATURE SHEET

SCALE: SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(28.-5-4.-5-3.-5-2.-5-1.-4)TR1	Franklin	28	2
CONTRACT NO. 78C34				
ILLINOIS FED. AID PROJECT				

Prepared By: 
DISTRICT STUDIES & PLANS ENGINEER

Examined By: 
DISTRICT LAND ACQUISITION ENGINEER

Examined By: 
DISTRICT PROGRAM DEVELOPMENT ENGINEER

Examined By:
DISTRICT OPERATIONS ENGINEER

Examined By: 
DISTRICT PROJECT IMPLEMENTATION ENGINEER

Examined By: 
DISTRICT CONSTRUCTION ENGINEER

Examined By: 
DISTRICT MATERIALS ENGINEER

GENERAL NOTES

COMMITMENTS:

TREES THREE (3) INCHES IN DIAMETER AND LARGER AT BREAST HEIGHT SHALL NOT BE CLEARED FROM APRIL 1ST THROUGH NOVEMBER 15TH OF ANY GIVEN YEAR.

SHOULD THE PROJECT REQUIRE TEMPORARY OR PERMANENT LIGHTING, ALL LIGHTING SHALL BE INSTALLED IN ACCORDANCE WITH FEDERAL HIGHWAY ADMINISTRATION GUIDE FOR BATS WHICH RECOMMENDS THAT LIGHTING DOES NOT INCREASE ILLUMINATION ABOVE AMBIENT CONDITIONS AND THAT INCORPORATES FULL CUT OFF, DOWNWARD FACING LIGHTS DIRECTED AWAY FROM FORESTED AREAS.

INDEX OF SHEETS

SHEET NO	DESCRIPTION
1	COVER SHEET
2	SIGNATURE SHEET
3	INDEX OF SHEETS, HIGHWAY STANDARDS, AND GENERAL NOTES
4	SUMMARY OF QUANTITIES
5-28	TREE REMOVAL SCHEDULES

ALIGNMENT DETAILS

NORTH BOUND LANES					
PROJECT BEGINS ==> > STA 289+22.60 WILLIAMSON CO. LINE					
*STATIONING DECREASES GOING NORTH					
EQN STA	48+09.47	BK	=	STA	47+95.24 AH
EQN STA	0+00.00	BK	=	STA	670+74.84 AH

HIGHWAY STANDARDS

000001-09 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701101-05 OFF-ROAD OPERATIONS, MULTILANE, 15 FT TO 24 IN FROM PAVEMENT EDGE
701106-02 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN15 FT AWAY
701400-12 APPROACH TO LANE CLOSURE, FREEWAY_EXPRESSWAY
701406-13 LANE CLOSURE, FREEWAY_EXPRESSWAY, DAY OPERATIONS ONLY
701411-09 LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS GREATER THAN 45 MPH
701428-01 TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY-EXPRESSWAY
701901-11 TRAFFIC CONTROL DEVICES

REV - MS

MODEL: INDEX [Sheet]
FILE NAME: c:\paw\work\paw\illinois\open\1227961\0976C34_ShtB_Index.dgn

	USER NAME = elise.lnop	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX, HIGHWAY STANDARDS, & GENERAL NOTES		F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -				57	(28,-5-4,-5-3,-5-2,-5-1,-4)TR1	Franklin	28	3
		CHECKED -	REVISED -		CONTRACT NO. 78C34						
	PLOT DATE = 5/12/2026	DATE -	REVISED -		SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	COUNTY:	FRANKLIN CO
				ROUTE:	FAI 57
				FUNDING:	100% STATE
				LOCATION:	RURAL
					LANDSCAPING 0031
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	33,206		33,206
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	25,491		25,491
67100100	MOBILIZATION	L SUM	1		1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2		2
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28		28

MODEL: SOQ [Sheet]
FILE NAME: c:\p\work\p\wdolkropen\1227961\0978C34_ShtC_SOQ.dgn

