

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE						
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A
80700140	GROUND ROD, 5/8" DIA. X 10FT	EACH	1						1		
80800525	TEMPORARY WOOD POLE 60 FT., CLASS 4 15 FT. MA	EACH	5						5		
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	869								
81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	775						775		
81302630	JUNCTION BOX, NON METALLIC, EMBEDDED IN STRUCTURE, 21"X11"X8"	EACH	1						1		
81400200	HEAVY-DUTY HANDHOLE	EACH	18						18		
81400205	HEAVY-DUTY HANDHOLE (SPECIAL)	EACH	2						2		
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	919						50		
81800700	AERIAL CABLE 3 1/C #2 ALUMINUM WITH MESSENGER WIRE	FOOT	700						700		
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	5						5		
84200800	POLE FOUNDATION, REMOVED	EACH	134	134							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	4,684	4,684							
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	1,041	1,041							
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	29	29							
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	202	202							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	9	9							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	4,615	4,615							
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	1,117	1,117							
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	2,126	2,126							
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	3,557	3,557							
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1,479	1,479							
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	1,786	1,786							
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	2,688	2,688							
550A0440	STORM SEWERS, CLASS A, TYPE 2 33"	FOOT	279	279							
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	3,886	3,886							
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	1,623	1,623							
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	163	163							
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	259	259							
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	257	257							
550A0700	STORM SEWERS, CLASS A, TYPE 3 21"	FOOT	133	133							
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	357	357							
550A0730	STORM SEWERS, CLASS A, TYPE 3 30"	FOOT	442	442							
550A0740	STORM SEWERS, CLASS A, TYPE 3 33"	FOOT	120	120							
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	321	321							

* - SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 SB EXPRESS LANE RECONSTRUCTION
 SUMMARY OF QUANTITIES
 SCHEDULE

SCALE: NTS
 DATE: 07/07/05
 DRAWN BY: RA
 CHECKED BY: JDC

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com



S0Q-05

6/29/2005 5:57:52 PM