F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	127
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62302 * (1818, ETC, 2324.6-1P)R-9

EXISTING STORM SEWER SCHEDULE

STATION	OFFSET	TO	STATION	OFFSET	STORM SEWER REMOVAL 8"	STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 27"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	STORM SEWER REMOVAL 42"	TRENCH BACKFILL (CY)
1445+33	8 RT		1445+37	1 RT		10										8.1
1447+50	56 LT		1447+55	39 LT			18									6.2
1447+55	56 LT		1447+60	8 RT			50									16.1
1449+83	92 LT		1450+05	82 LT		21										2
1449+98	77 LT		1450+05	82 LT		7										0.7
1450+05	44 LT		1450+05	82 LT		39										3.6
1449+81	52 LT		1450+05	44 LT		24										1.2
1450+05	82 LT		1450+40	84 LT			35									4.3
1450+33	43 LT		1450+33	8 RT		54										21.8
1450+33	8 RT		1450+47	8 RT		16										7
1450+40	84 LT		1450+47	8 RT									88			22
1450+51	53 LT		1450+51	78 LT		26										0
1450+51	78 LT		1450+40	84 LT		11										0.6
1450+95	43 LT		1450+95	4 RT		48										21.9
1450+95	4 RT		1450+47	8 RT		48										22.4
1450+95	84 LT		1451+08	78 LT		15										7.6
1451+08	84 LT		1451+08	78 LT		6										3
1453+28	76 LT		1451+08	78 LT					219							223.1
1453+38	8 RT		1453+28	76 LT		88										75.7
1453+38	79 LT		1453+28	76 LT		9										8.6
1457+45	66 LT		1457+45	59 LT				8								7.5
1457+45	59 LT		1457+50	53 LT				8								7.5
1457+50	53 LT		1459+77	51 LT					226							137.7
1459+70	65 LT		1459+69	57 LT			9									0
1459+69	57 LT		1459+77	51 LT			8									3.6
1459+69	8 RT		1459+77	51 LT		61										22.8
1459+77	51 LT		1460+53	53 LT							75					45.6
1460+32	65 LT		1460+32	57 LT			9									3.6
1460+32	57 LT		1460+53	53 LT			11									4.9
1460+53	53 LT		1460+53	8 RT									62			43.4
1460+89	53 LT		1460+53	53 LT		36										15.3
1460+96	8 RT		1460+89	53 LT		62										22.5
1460+96	56 LT		1460+89	53 LT		7										2.8
1462+77	9 RT		1462+85	53 LT			62									19.3
1462+85	53 LT		1463+45	52 LT							60					34.7
1463+37	6 RT		1463+45	52 LT		60										24.9
1463+45	52 LT		1465+17	52 LT							173					0
1465+13	51 LT		1465+17	52 LT		5										0
1465+22	8 RT		1465+17	52 LT		61										56.3
1465+17	52 LT		1465+17	5 RT									57			0
1469+31	8 RT		1469+29	56 LT		66										0
1469+29	56 LT		1469+57	53 LT			28									14.9
1469+31	53 LT		1469+57	53 LT			28									0
1469+57	53 LT		1471+18	52 LT				160								0
1471+10	56 LT		1471+18	52 LT			8									3.6
1471+18	8 RT		1471+18	52 LT		61										0
1471+18	52 LT		1473+17	53 LT					201							0
1473+03	8 RT		1473+03	56 LT		65										0
1473+03	56 LT		1473+17	53 LT			14									4.2
1473+17	53 LT		1473+11	4 RT									66			30.8
1473+55	53 LT		1473+17	53 LT				38								13.3
1473+52	62 LT		1473+55	53 LT		3										0.8
1473+59	2 RT		1473+58	8 RT		2										0.4
1473+95	56 LT		1473+55	53 LT		39										9.3
1475+93	8 RT		1476+56	5 RT			40									9.3
1476+56	5 RT		1476+51	53 LT				60								21.3
1476+45	56 LT		1476+51	53 LT			7									2.4
1476+51	53 LT		1477+89	52 LT					139							0
1477+89	52 LT		1477+95	2 RT									55			64.8
1478+72	52 LT		1477+89	52 LT				84								0
1478+72	8 RT		1478+72	52 LT		57										48.1
1478+79	56 LT		1478+72	52 LT			6									5.6

STATION	OFFSET	TO	STATION	OFFSET	STORM SEWER REMOVAL 8"	STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 27"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	STORM SEWER REMOVAL 42"	TRENCH BACKFILL (CY)
1481+20	5 RT		1481+18	57 LT			62									7.6
1481+18	57 LT		1481+53	52 LT				37								9
1481+53	52 LT		1482+83	53 LT					128							0
1482+83	53 LT		1482+83	3 RT									55			34.8
1483+47	53 LT		1482+83	53 LT					64							0
1483+55	56 LT		1483+47	53 LT			8									3.9
1485+83	53 LT		1483+47	53 LT				237								0
1485+90	8 RT		1485+83	53 LT		62										31.5
1485+90	56 LT		1485+83	53 LT			8									7.3
1489+63	8 RT		1489+78	53 LT		64										25.9
1490+69	52 LT		1491+91	47 LT			123									0
1491+96	8 RT		1491+91	47 LT		57										25.4
1491+96	56 LT		1491+91	47 LT		11										5.4
1491+91	47 LT		1494+01	51 LT					211							0
1494+01	51 LT		1494+01	8 RT							59					30.6
1494+09	8 RT		1494+09	57 LT				68								25.8
1494+09	57 LT		1494+01	51 LT			11									4.4
1496+42	59 LT		1496+50	55 LT			8									9.9
1496+44	8 RT		1496+50	55 LT		62										68.1
1496+50	55 LT		1497+89	53 LT				140								179.2
1497+89	53 LT		1498+70	53 LT				91								0
1498+76	8 RT		1498+73	62 LT		65										59
1498+73	62 LT		1498+70	53 LT			10									10.5
1498+70	53 LT		1498+83	4 RT							56					70.7
1500+64	53 LT		1498+70	53 LT					183							172.8
1500+72	57 LT		1500+64	53 LT		10										3.7
1500+72	8 RT		1500+64	53 LT				62								25
1502+66	8 RT		1502+80	54 LT		65										0
1502+80	54 LT		1503+55	53 LT				73								19.6
1503+48	56 LT		1503+55	53 LT		7										1.5
1503+58	8 RT		1503+55	53 LT			61									15.6
1503+55	53 LT		1504+25	53 LT							70					41.5
1504+17	8 RT		1504+19	58 LT		65										0.7
1504+19	58 LT		1504+25	53 LT			6									1.1
1504+25	53 LT		1504+25	4 RT									57			43.7
1507+21	8 RT		1507+35	54 LT		64										12.6
1507+24	58 LT		1507+35	54 LT			10									2.4
1507+35	54 LT		1508+48	58 LT					115							52.2
1508+80	8 RT		1508+48	58 LT		66										2.7
1508+56	62 LT		1508+48	58 LT		8										0.4
1508+48	58 LT		1510+26	62 LT							178					221.2
1510+26	62 LT		1510+26	6 RT									68			110.3
1510+35	8 RT		1510+35	67 LT		72										26.9
1510+35	67 LT		1510+26	62 LT		7										3.2
1511+54	71 LT		1510+26	62 LT							128					92.9
1511+88	36 LT		1511+83	41 LT		5										0
1511+83	41 LT		1511+54	71 LT		47										2.4
1512+72	8 RT		1512+86	77 LT		87										35.2
1512+79	81 LT		1512+86	77 LT				9								4.8
1512+86	77 LT		1511+54	71 LT					134							85.1
1513+87	45 LT		1514+12	87 LT		61										15.2
1513+87	5 RT		1512+72	8 RT		94										0
1514+12	87 LT		1512+86	77 LT		125										55.7
1516+59	71 LT		1517+28	53 LT		68										9.9
1517+28	53 LT		1517+33	43 LT		15										5.4
1517+18	8 RT		1517+28	46 LT			54									19.2
1517+33	43 LT		1517+33	5 RT							48					27.2
1520+17	46 LT		1520+23	42 LT					14							6.5
1520+23	7 RT		1520+23	42 LT				50								19.6
1520+23	42 LT		1521+57	43 LT							132					78.2
1521+57	67 LT		1521+57	43 LT		23										4.5
1521+57	43 LT		1522+65	42 LT							109					66.2

DS-7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION

DRAINAGE SCHEDULE
EXISTING STORM SEWER REMOVAL

SCALE: 1" = N.T.S — DRAWN BY: MJO
DATE: 7/7/05 — CHECKED BY: LPN

Edwards AND Kelcey
ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

P:\03009\0375\Con 14\5\CADD\5\05\50042E.SH
05/27/2025 07:02:06 PM