

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	598	129
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
	62302	(1818, ETC, 2324.6-1PIR-8		

EXISTING STORM SEWER SCHEDULE

STATION	OFFSET	TO	STATION	OFFSET	STORM SEWER REMOVAL 8"	STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 27"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	STORM SEWER REMOVAL 42"	TRENCH BACKFILL (CY)
1530+20.5	4.5' RT		1530+14.0	53.4' LT			54.3									7.1
1531+45.2	5.9' RT		1531+44.5	43.2' LT		45.2										
1531+44.5	43.2' LT		1531+44.5	52.3' LT		5.0										
1532+63.8	5.9' RT		1532+80.1	5.1' RT		12.3										
1532+63.8	5.9' RT		1532+70.1	56.8' LT			61.5									49.8
1534+09.3	29.5' LT		1534+79.5	32.3' LT		66.3										24.3
1534+78.1	13.7' RT		1534+79.5	32.3' LT						42.1						78.1
1534+79.5	32.3' LT		1535+33.9	32.1' LT				50.4								52.0
1535+28.5	15.0' RT		1535+38.3	25.0' LT			37.2									9.9
1535+33.9	32.1' LT		1535+39.4	44.5' LT				9.3								7.3
1535+33.9	32.1' LT		1536+58.7	30.6' LT				120.3								52.2
1536+52.6	25.5' LT		1536+58.7	30.6' LT		3.9										0.2
1536+58.7	30.6' LT		1537+71.9	31.6' LT			106.8									51.8
1537+60.7	12.6' RT		1537+66.9	26.2' LT		35.2										2.5
1537+66.9	26.2' LT		1537+71.9	31.6' LT		3.3										0.1
1539+08.4	15.8' RT		1538+97.8	18.8' RT			6.1									1.1
1539+02.4	28.3' LT		1539+10.4	33.8' LT		5.6										0.5
1539+10.4	33.8' LT		1539+64.7	33.7' LT			49.0									27.0
1540+37.1	31.7' LT		1540+43.6	36.0' LT		3.6										0.2
1540+43.6	36.0' LT		1540+41.5	61.2' LT			21.4									7.2
1540+30.7	61.0' LT		1540+41.5	61.2' LT		6.3										
1540+43.6	36.0' LT		1541+53.8	39.4' LT				103.5								85.8
1541+53.8	39.4' LT		1541+58.4	35.8' LT		1.8										
1541+58.4	35.8' LT		1542+85.9	40.7' LT			124.9									106.3
1542+85.9	40.7' LT		1542+99.1	85.4' LT			42.7									35.0
1542+85.9	40.7' LT		1542+92.8	36.3' LT		4.2										1.1
1542+92.8	36.3' LT		1542+93.6	7.2' RT		39.5										1.5
1546+70.5	7.9' RT		1546+51.5	73.2' LT			79.3									42.3
1546+51.5	73.2' LT		1546+64.3	69.4' LT			9.4									6.3
1546+55.6	80.7' LT		1546+64.3	69.4' LT			10.3									4.6
1546+64.3	69.4' LT		1548+47.1	58.1' LT				179.2								110.5
1548+47.1	58.1' LT		1548+52.0	73.5' LT		12.0										2.7
1548+47.1	58.1' LT		1548+55.1	64.4' LT			6.0									1.6
1548+55.1	64.4' LT		1548+68.9	7.8' RT		69.5										10.5
1551+45.9	7.4' RT		1551+45.1	57.8' LT			61.2									21.9
1551+45.1	57.8' LT		1551+58.1	52.8' LT			10.0									
1551+51.4	67.0' LT		1551+58.1	52.8' LT			11.7									
1551+51.4	67.0' LT		1551+58.1	66.9' LT			2.7									
1551+58.1	52.8' LT		1553+80.2	52.0' LT				218.0								126.5
1553+80.2	52.0' LT		1554+67.0	53.2' LT							82.8					103.7
1554+67.0	53.2' LT		1554+76.8	67.1' LT		13.0										1.7
1554+67.0	53.2' LT		1554+76.6	57.8' LT			6.7									1.0
1554+76.6	57.8' LT		1554+74.9	7.7' RT		61.5										
1555+32.0	7.6' RT		1555+44.8	57.4' LT			62.3									16.1
1555+35.8	54.3' LT		1554+67.0	53.2' LT							64.9					69.9

STATION	OFFSET	TO	STATION	OFFSET	STORM SEWER REMOVAL 8"	STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 21"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 27"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	STORM SEWER REMOVAL 42"	TRENCH BACKFILL (CY)
1555+35.8	54.3' LT		1555+44.8	57.4' LT			5.6									
1556+53.7	53.9' LT		1555+35.8	54.3' LT							113.9					109.2
1555+35.8	54.3' LT		1555+41.3	67.2' LT				10.0								
1556+53.7	53.9' LT		1556+58.7	67.1' LT				10.1								3.0
1556+53.7	53.9' LT		1556+59.6	57.3' LT			2.8									0.5
1556+59.6	57.3' LT		1556+68.3	7.7' RT			61.6									29.8
1558+04.5	7.7' RT		1558+02.6	57.7' LT		61.5										
1558+02.6	57.7' LT		1558+12.0	53.7' LT			6.2									
1558+04.3	67.2' LT		1558+12.0	53.7' LT		11.5										1.8
1558+12.0	53.7' LT		1560+10.0	52.7' LT				194.0								83.3
1560+10.0	52.7' LT		1560+05.4	67.2' LT			11.2									4.2
1560+10.0	52.7' LT		1560+14.8	57.8' LT			3.1									0.5
1560+14.8	57.8' LT		1560+15.9	7.9' RT		61.7										23.6
1562+93.0	8.0' RT		1562+89.2	57.8' LT		62.0										
1562+89.2	57.8' LT		1562+96.3	54.3' LT			3.9									0.3
1562+89.1	67.4' LT		1562+96.3	54.3' LT		11.0										1.2
1562+96.3	54.3' LT		1564+60.6	51.8' LT						160.4						
1564+60.6	51.8' LT		1564+92.6	67.3' LT			31.5									14.1
1564+60.6	51.8' LT		1564+92.8	57.9' LT			28.8									
1564+93.1	1.8' RT		1564+92.8	57.9' LT		55.7										8.6
1566+74.3	7.6' RT		1566+78.1	58.1' LT		61.9										
1566+78.1	58.1' LT		1566+86.0	56.7' LT			4.1									0.4
1566+79.6	67.5' LT		1566+86.0	56.7' LT			8.6									1.5
1566+86.0	56.7' LT		1567+65.9	54.7' LT				76.0								31.6
1567+56.5	57.7' LT		1567+65.6	6.1' RT		60.5										45.3
1567+56.5	57.7' LT		1567+65.9	54.7' LT		5.9										
1567+55.6	67.4' LT		1567+65.9	54.7' LT				12.5								5.3
1567+65.9	54.7' LT		1568+35.3	52.0' LT						65.4						41.1
1568+25.7	57.0' LT		1568+26.8	1.6' RT		54.7										17.6
1568+26.8	1.6' RT		1568+29.4	7.8' RT		2.7										0.3
1568+25.7	57.0' LT		1568+35.3	52.0' LT			6.9									1.4
1568+21.4	67.3' LT		1568+35.3	52.0' LT		16.7										2.1
1568+35.3	52.0' LT		1570+13.1	53.5' LT					173.7							89.4
1570+13.1	53.5' LT		1570+13.0	7.7' RT			57.3									25.1
1570+13.1	53.5' LT		1570+18.2	57.7' LT			2.6									0.3
1570+13.1	53.5' LT		1570+19.1	67.1' LT			10.9									2.5
1567+27.7	5.7' RT		1567+65.6	6.1' RT		33.9										11.2
1572+30.0	7.6' RT		1572+27.9	57.6' LT		61.2										
1572+27.9	57.6' LT		1572+39.9	52.5' LT			9.0									1.7
1572+29.8	66.9' LT		1572+39.9	52.5' LT				13.6								3.1
1572+39.9	52.5' LT		1573+57.6	54.3' LT								113.7				206.2
1573+57.6	54.3' LT		1574+77.0	54.4' LT								115.4				171.7
1574+77.0	54.4' LT		1574+77.1	6.2' RT			56.6									
1574+77.1	6.2' RT		1575+03.4	12.4' RT			23.0									3.1
1574+77.0	54.4' LT		1575+91.3	53.9' LT							110.3					112.7

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 SB EXPRESS LANE RECONSTRUCTION
 DRAINAGE SCHEDULES
 EXISTING STORM SEWER REMOVAL
 SCALE: 1"=N.T.S. DRAWN BY: OC
 DATE: 07/07/05 CHECKED BY: DDM

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com

DS-09
 06/29/2005 03:53:37 PM