

SCHEDULE OF STORM SEWERS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	598	150
STA.		TO STA.		
62302		* (1818, ETC, 2324.6-1)PR-9		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T1 27	SS CL A T2 12	SS CL A T2 15	SS CL A T2 18	SS CL A T2 21	SS CL A T2 24	SS CL A T2 27	SS CL A T2 30	SS CL A T2 33	SS CL A T2 36	SS CL A T2 42	SS CL A T2 48	SS CL A T3 21	SS CL A T3 24	SS CL A T3 27	SS CL A T3 30	SS CL A T3 36	TRENCH BACKFILL
25-07	25-06	1.00	40																					7.8
25-08	25-07	1.03	66																					11.4
25-09	25-06	0.58									127													209.7
25-10	25-09	0.40		24																				5.1
25-11	25-09	0.58																	133					229.8
25-12	25-11	0.50	45																					8.7
25-13	25-11	0.90		2																				0.5
25-14	25-04	0.31												137										232.6
EXIST.	25-12	1.00	66																					10.0
EXIST.	25-13	0.90		29																				5.7
EXIST.	26-01	1.00						100																25.7
25-15	25-16	1.00	54																					9.2
25-16	25-06	1.00	1																					0.5
25-17	25-09	1.00	2																					0.5
26-01	26-02	0.64						58																16.1
26-02	26-04	0.64							16															6.0
26-04	26-03	0.48											167											290.9
EXIST.	26-06	0.50			7																			2.3
26-06	26-07	0.72									14													12.1
26-07	26-03	0.90									3													2.9
26-05	26-03	0.50	43																					8.3
26-08	26-11	0.60	17																					3.3
26-11	26-09	0.70						2																0.5
26-09	27-02	0.30															74							132.3
26-10	26-09	0.50	42																					9.3
26-03	26-09	0.48											194											339.0
27-01	27-02	1.00			3																			0.7
27-02	27-04	0.15																						169.9
27-03	27-04	0.60	17												125									3.7
27-04	27-07	0.2													106									144.1
27-05	27-04	0.50	42																					7.8
27-06	27-07	0.90		2																				1.0
27-07	27-08	0.20														37								43.0
27-08	27-14	0.20													77									74.2
27-09	27-14	2.00	2																					1.0
27-10	27-12	1.00		45																				15.6
27-11	27-10	0.36		22																				18.3
27-12	28-08	0.15																						115.7
27-13	27-12	2.00	2																					1.0
27-14	27-12	0.40													172									123.5
28-01	28-08	2.00	5																					1.0
28-03	28-04	0.50	11																					1.7
28-04	28-02	1.00		2																				1.0
28-09	28-02	2.00	8																					1.7
28-10	28-15	0.65						47																14.1
28-05	28-07	0.50	10																					1.7
28-06	28-07	2.00		3																				1.0
28-07	28-02	0.17																						36.0
28-08	28-02	0.17																						41.5
28-14	28-13	0.50	3																					0.9
28-15	28-13	0.22													104									95.2
28-13	28-02	0.11																						44.6
28-12	28-11	0.60	53																					9.2
28-11	28-06	0.82	11																					1.7
1530+00	28-15	0.10													70									

NOTE: * INDICATED STRUCTURE HAS BEEN CONSTRUCTED IN CONTRACT 62300



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
SB EXPRESS LANE RECONSTRUCTION

DRAINAGE SCHEDULE
PROPOSED STORM SEWER PIPES

SCALE: DRAWN BY:
DATE: 7/7/05 CHECKED BY:

DS-30

06/27/2005 07:50:54 PM