INDEX OF SHEETS

CONT. INDEX OF SHEETS

L	IST	0F	
STATE	STA	ND	ARDS

F.A.I. SECTION	Ν	COUN	ΤY	TOTAL	SHEET NO.
94/90 * 2003-0	28F	COO	K	419	2
STA.	1	O STA.			
FED. ROAD DIST. NO.	ILLIN	DIS FED.	AID	PROJECT	

62580

SHE	ET	NO.	DESCRIPTION		
2 3	TO	5	INDEX OF SHEETS, GENERAL NOTES AND STATE STANDARDS SUMMARY OF QUANTITIES		
6	TO	12	CIVIL SCHEDULES		
	TO		ALIGNMENT PLAN		
	TO	22	EXISTING AND PROPOSED PLAN		
23			PROPOSED MAINTENANCE OF TRAFFIC CROSSOVER BETWEEN 31ST ST AND 28T		
24	т.	00	PROPOSED MAINTENANCE OF TRAFFIC CROSSOVER BETWEEN 13TH ST AND ROC)SEVEL 1	RD
	TO	28	MAINTENANCE OF TRAFFIC PLAN GENERAL NOTES AND TYPICAL SECTIONS		
	TO TO	43 47	MAINTENANCE OF TRAFFIC PLAN - STAGE I		
	TO		MAINTENANCE OF TRAFFIC PLAN - STAGE IA MAINTENANCE OF TRAFFIC PLAN - STAGE IIA		
	TO	75	MAINTENANCE OF TRAFFIC PLAN - STAGE IIB		
	TO		MAINTENANCE OF TRAFFIC CONTRACT 62300, INFORMATION ONLY		
		82B	MAINTENANCE OF TRAFFIC CONTRACT 62300 SUBSTAGE A, INFORMATION ONL'	Y	
	TO		MAINTENANCE OF TRAFFIC CONTRACT 62302, INFORMATION ONLY		
91			DETOUR ROUTE FOR RAMP E		
92			DETOUR ROUTE FOR RAMP B		
93			DETOUR ROUTE FOR RAMP D		
94			DETOUR ROUTE FOR 18TH ST ENTRANCE RAMP TO WB I-94-90		
95			DETOUR ROUTE FOR WB I-94-90 EXIT TO ROOSEVELT ROAD		
96			DETOUR ROUTE FOR WB I-94-90 EXIT TO S CANAL AVE		
97			MARTIN LUTHER KING TURN AROUND, FOR INFORMATION ONLY		
98	т.	447	CIVIL DETAILS		
l		113	PROPOSED PAVEMENT MARKING PLAN	G	EN
)		121 128	TEMPORARY INFORMATION SIGNING EXISTING DRAINAGE SYSTEM DETAILS		
122	10	120	VIADUCT KEY PLAN SHEET	1.	THE
130			GENERAL NOTES FOR STRUCTURES		BEFO
131			TOTAL BILL OF MATERIALS		FIEL
132	ТО	142	GENERAL PLANS AND ELEVATIONS		CON
143			PARTIAL DECK PLANS		
160			LOCATION & DESIGNATION OF JOINTS 1.	2.	THE
161			LOCATION & DESIGNATION OF JOINTS 2		
162			TYPICAL SECTIONS EXISTING JOINTS	3.	THE
163			TYPICAL SECTIONS PROPOSED JOINTS		UTIL
164			TYPICAL PARTIAL PLAN AT STAGED ROADWAYS		
165			TYPICAL PARTIAL PLAN AT NON STAGED ROADWAYS	4.	-
166			TYPICAL PARTIAL PLAN AT STAGED & NON STAGED ROADWAYS		*-
167			SHEET DELETED	5.	WHEN
168 169			CLOSURE WALL GENERAL DETAILS SCARIFICATION & OVERLAY TRANSITION DETAILS	J.	ADV
170			TYPICAL CROSS SECTIONS & SILICONE JOINT SEALER DETAIL		AUT
170A			PARAPET REPAIRS, SILICONE JOINT SEALER & JOINT REMOVAL DETAILS	6.	THE
171	ΤO	177	BAR DETAILS	••	ANY
178	10	111	BILL OF MATERIALS & BAR SCHEDULE		
	ΤO	235	FINGER PLATE JOINT PLANS	7.	THE
		243	FRAMING PLAN		EXIS
-		249	STEEL REPAIR DETAILS		ALL
250			BEARING DETAILS		WATI
25.5	10	299	PIER REPAIRS		A TE

SHEET	NO.	DESCRIPTION
300 TO		DRAINAGE REPAIR DETAILS
	308	ADJUSTING DRAINAGE SCUPPER DETAILS
309		ANCHOR BOLT DETAILS FOR BEARINGS
310		BAR SPLICER ASSEMBLY DETAILS
311		TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
312		BRIDGE JOINT SYSTEM - FIXED
313		BRIDGE JOINT SYSTEM - EXPANSION (PREFORMED JOINT SEAL)
314		BRIDGE JOINT SYSTEM - EXPANSION (ALTERNATE - STRIP SEAL)
314A		STRIP SEAL EXPANSION JOINT ASSEMBLY DETAILS
315 TO	383	EXISTING PLAN INFORMATION
384 TO	410	TRAFFIC SYSTEM CENTER
411		TC-8 ENTRANCE AND EXIT RAMP CLOSURE DETAILS
412		TC-11 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT)
413 TO	414	TC-12 MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS
415		TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS
416		TC-16 PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
417		TC-17 TRAFFIC CONTROL FOR SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES
418		TC-18 SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
419		TC-22 TEMPORARY INFORMATION SIGNING

GENERAL NOTES

- 1. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE RESPECTIVE UTILITY COMPANIES AND THE CITY OF CHICAGO. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL THE CHICAGO UTILITY ALERT NETWORK AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE, CABLE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED). CONTACT THE CHICAGO DEPARMENT OF WATER MANAGEMENT PERMIT SECTION AT (312) 747-7893 FOR WATER AND SEWER LOCATIONS.
- 2, THE CONTRACTOR SHALL NOT SET UP A YARD OR FIELD OFFICE ON I.D.O.T. PROPERTY WITHOUT WRITTEN PERMISSION FROM I.D.O.T.
- 3. THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ABUTTING PROPERTY, UTILITIES, PEDESTRIANS, AND VEHICULAR TRAFFIC.
- 5. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTION IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND THE ADJOINING COMMERCIAL AND RESIDENTIAL AREAS.
- 6. THE CONTRACTOR SHALL USE CARE IN GRADING OR EXCAVATING NEAR ANY AND ALL EXISTING ITEMS THAT WILL NOT BE REMOVED.

 ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
- 7. THE CONTRACTOR SHALL MAINTAIN THE SURFACE DRAINAGE OF ALL ROADWAYS & BRIDGES DURING CONSTRUCTION OF THIS PROJECT. WHEN EXISTING DRAINAGE FACILITIES ARE DISTURBED, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY OUTLETS AND CONNECTORS FOR ALL PRIVATE OR PUBLIC DRAINS, SEWERS, INLETS AND CATCH BASINS. THE CONTRACTOR SHALL PROVIDE FACILITIES TO TAKE IN ALL STORM WATER WHICH WILL BE RECEIVED BY THESE DRAINS AND SEWERS AND DISCHARGE THE SAME. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN A TEMPORARY OUTLET, AND BE PREPARED AT ALL TIMES TO DISPOSE OF THE WATER RECEIVED FROM THESE TEMPORARY CONNECTIONS UNTIL INSTALLATIONS ARE COMPLETE INCLUDING PAVEMENT. THIS WORK SHALL NOT BE PAID FOR DIRECTLY BUT SHALL BE CONSIDERED INCLUDED IN THE CONTRACT.
- 8. THE UNIT WEIGHT USED FOR ALL BITUMINOUS SURFACE MIXTURES IS 112 LB/SQ YD/IN.
- 9. CRUSHING PLANT AND CONCRETE PLANT LOCATIONS REQUIRE CITY OF CHICAGO APPROVAL.
- 10. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ANY SEDIMENT ACCUMULATION IN THE VICINITY OF THE CATCH BASINS THAT REQUIRE CLEANING AS DIRECTED BY THE ENGINEER. LIDS SHALL BE RESET AS REQUIRED. COST SHALL BE INCLUDED WITH "CATCH BASINS TO BE CLEANED".

000001-04	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
635006 -02	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011 -01	REFLECTOR MARKER AND MOUNTING DETAILS
701001- 01	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006- 02	OFF-ROAD OPERATIONS, 2L, 2W, 4.5 M (15') TO 600 MM (24") FROM PAVEMENT EDGE
701101- 01	OFF-ROAD OPERATIONS, MULTILANE, 4.5 M (15") TO 600 MM (24") FROM PAVEMENT EDGE
701301 -02	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306- 01	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS > OR = 45 MPH
701311- 02	LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
701400 -<i>0</i>2	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401 -<i>03</i>	LANE CLOSURE, FREEWAY/EXPRESSWAY
701402 -<i>05</i>	LANE CLOSURES, FREEWAY/EXPRESSWAY, WITH BARRIER
701411 - 03	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > OR = 45 MPH
701426 - 02	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS > OR =45MPH
701501- 03	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701601 - 04	URBAN LANE CLOSURE, MULTILANE 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701606 -04	URBAN LANE CLOSURE, MUILTILANE, 2W WITH MOUNTABLE MEDIAN
701701 - 04	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801 - 03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001 -<i>05</i>	TRAFFIC CONTROL DEVICES
704001- 02	TEMPORARY CONCRETE BARRIER
720001	SIGN PANEL MOUNTING DETAILS
720006	SIGN PANEL ERECTION DETAILS
720011	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
780001- 0 1	TYPICAL PAVEMENT MARKINGS

PROJECT COMMITMENTS

IDOT HAD MADE THE FOLLOWING COMMITMENTS FOR THIS PROJECT:

IDOT HAS COMMITTED TO ADDRESS CONSTRUCTION RELATED AIR QUALITY CONCERNS. THESE STRATEGIES INCLUDE REQUIRING DETAILED DUST CONTROL PLANS, REQUIRING THE USE OF CLEANER BURNING DIESEL FUELS ON CERTAIN DIESEL POWERED CONSTRUCTION EQUIPMENT AND/OR THE INSTALLATION OF EXAUST EMMISSION SCRUBBERS, AND THE REDUCTION OF CONSTRUCTION EQUIPMENT IDLING TIMES. THESE STRATEGIES ARE ADDRESSED IN SPECIAL PROVISIONS INCLUDED IN THIS CONTRACT AND DEVELOPED FOR THE DAN RYAN RECONSTRUCTION PROJECT.

		GNO-01	
REVISIONS	ILLINOIS DEPARTMENT	OF TRANSPORTATION	
NAME DATE	F.A.I. 94/90 (DAN F	RYAN EXPRESSWAY)	P.M
	NB DAN RYAN EL	EVATED BRIDGE	3,43,19
	REPAIR FROM 15TH	10 281H STREETS	A.
	INDEX OF SHEETS,	GENERAL NOTES	
	AND STATE :	STANDARDS	B
	SCALE: =NTS	DRAWN BY: RA	8
	DATE: 8/12/2005	CHECKED BY: RS	8/1

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312, 228, 0100
www.bbandainc.com