
F.A.I.	SECTION	٠ T	COUNT	Y	TOTAL SHEETS	SHEET NO. 308	
94/90	2003-0286		COOK		419		
STA.		TO	STA.				
FED. RO	D DIST. NO.	ILLINOI:	FED.	AID	PROJECT		


62580

BILL OF MATERIAL

ITEM DESCRIPTION	UNIT	TOTAL	SN 016-0137	SN 016-1110	SN 016-1111	SN 016-1112	SN 016-1113	SN 016-1114	SN 016-1115	SN 016-1116	SN 016-1117	SN 016-1118	SN 016-1047	SN 016-1059	SN 016-1070	SN 016-1140
ADJUSTING DRAINAGE SCUPPERS, TYPE A	EACH	107	10	8	11	26	3	-	8	8	27	2	2	-		2
ADJUSTING DRAINAGE SCUPPERS, TYPE B	EACH	26	-	-	-	1	2	10	3	-	7	3	-	-	-	-
ADJUSTING DRAINAGE SCUPPERS TYPE C	FACH	109	11	11	12	12	12	-	20	8	_	16	1	-	4	1 2



PLAN • TYPE C SCUPPER



DRAINAGE SCUPPER DETAILS - TYPE C

Vane Grate 3943-0002 machined to fit

Exist. Parapet to remain - Side Grate (see note 2) Seal gap with approved -New Adjusting Ring sealant as reg'd. -Microsilica Concrete Overlay 21₄" - Hydroscarification 1₂" New Vane Grate Exist, Scupper Frame (Neenah 3943-0002)

SECTION THRU TYPE C SCUPPER

2. At SN 016-1070 (Ramp D), scupper plates (side grates) at the side of the parapet are missing. The contractor shall verify location, type and dimensions for these side plates before ordering the material. The cost for furnishing and installing these grates shall be included in "Adjusting Drainage Scuppers" of the type specified. EEstimated No. Required: Three (3) Type CJ.

1. For the scuppers marked on plan sheets SN 016-1111 (3 Req'd) as 🔄 , the contractor shall verify the exact location, type and dimensions before he orders the material. The quantity and pay

item is included in "Adjust Drainage Scuppers, Type A".

- 3. For scupper locations, see Partial Deck Plan Sheets.
- 4. A paint stripe shall be applied over the existing stripe to the face of the Concrete Barrier Wall at all drainage scupper locations. The stripe shall be 4" wide x 12 " long and extend vertically at 90 degrees from the top edge of the barrier. The paint color shall be specified by the Engineer. Cost of the strip is to be included in "Adjusting Drainage Scuppers" of the type specified.

REVISIONS NAME	DATE	ILLINOIS DEPARTMENT OF A.I. 94/90 (DAN R NB DAN RYAN ELE REPAIR FROM 15TH	YAN EXPRESSWAY) EVATED BRIDGE TO 28TH STREETS	11:54:52 AM
		ADJUSTING DRAII DETA: SCALE: N/A DATE: 8/12/2005	rı s	8/11/2005

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com