F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-067L	COOK	35	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62806

URBAN

100% STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	DOT WORK LIGHTING Y030-1E
67100100	MOBILIZATION	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8
80700110	GROUND ROD, 3/4" DIA. X 10'-0" LENGTH	EACH	73	73
X0324667	CONCRETE FOUNDATION, 20" DIAMETER, 1" ANCHOR RODS, 10" BOLT CIRCLE	FOOT	365	365
X0323768	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID	EACH	11	11
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	1	1
X0324435	CLEAN EXISTING MANHOLE OR HANDHOLE	EACH	1	1
X0324662	CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 1.25"	FOOT	6936	6936
X0324934	CONDUIT, POLYETHYLENE, DIRECTIONAL BORING, 2"	FOOT	133	133
X0320001	PVC CONDUIT IN TRENCH, 2" DIA. (SCHEDULE 40)	FOOT	105	105
81000600	CONDUIT IN TRENCH, 2" DIA. GALVANIZED STEEL	FOOT	10	10
X0324354	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	115	115
X8950075	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	1	1
84200500	REMOVE EXISTING LIGHTING UNIT AND SALVAGE	EACH	72	72
X0324434	REMOVE EXISTING STREET LIGHTING UNIT FOUNDATION	EACH	72	72

~~⊙ YOBO~~

~~□ NON-PARTICIPATING~~

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59th ST TO 47th ST (FRONTAGE ROAD)
CITY OF CHICAGO LIGHTING CONDUIT & FOUNDATIONS
WELLS STREET

SUMMARY OF QUANTITIES

SCALE: NONE | DRAWN BY: CJM
DATE: February 11, 2005 | CHECKED BY: WDS

\\ctech-nt7\p40466\p40466\elec\V4-nt19-stl\contract 90\2005\02-02-05 09:01:44 NM