CONTRACT 62884

INDEX OF SHEETS

LIST OF STATE STANDARDS

| SHEET NO. | DESCRIPTION | STANDARD NO. | DESCRIPTION |
|-----------|--|--------------------|--|
| 1 | COVER SHEET | 000001-04 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 2 | INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES | 630001- 05 | STEEL PLATE BEAM GUARDRAIL |
| 3 | SUMMARY OF QUANTITIES | | The second secon |
| 4 | TYPICAL SECTIONS | 635006 -02 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 5-9 | EXISTING AND PROPOSED ROADWAY PLAN | 635011 <i>-0</i> 1 | REFLECTOR MARKER AND MOUNTING DETAILS |
| 10 | PIPE UNDERDRAIN OUTLET EXTENSION DETAILS | 701101- 01 | OFF-RD OPERATIONS, MULTILANE LESS THAN 4.5 M (15') AWAY FOR SPEEDS > 45 MPH |
| 11 | CONCRETE COLLAR AND INLET BOX DETAILS | 701400 <i>-0</i> 2 | APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY |
| 12-13 | MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS | 701400 02 | |
| 14 | TRAFFIC CONTROL FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES | 701401- 03 | LANE CLOSURE, FREEWAY/EXPRESSWAY |
| 17 | | 702001- 05 | TRAFFIC CONTROL DEVICES |

| INTERSTATE 55 | | | | | | |
|---------------------------|---------------------------------|------------------------------------|--|-------------------------|--|--|
| INTERSTATE 55 STATIONS | EARTH EXCAVATION (CU. YD) | UNSUITABLE MATERIAL (CU.YD.) | EXCAVATION USED AS EMBANKMENT (SHRINKAGE 15%) (CU.YD.) | EMBANKMENT (CU. YD.) | EARTH WORK BALANCE SURPLUS (+) OR SHORTAGE (-) (CU. YD.) | |
| 1268+25 TO 1272+00 | 19.1 | 69.4 | 16.2 | 104.8 | -88.6 | |
| 1272+00 TO 1287+00 | 68.0 | 277.8 | 57.8 | 498.5 | -440.7 | |
| 1287+00 TO 1302+00 | 63.5 | 277.8 | 54.0 | 519.9 | -465.9 | |
| 1302+00 TO 1317+00 | 70.6 | 277.8 | 60.0 | 475.0 | -415.0 | |
| 1317+00 TO 1332+00 | 97.3 | 277.8 | 82.7 | 378.4 | -295.7 | |
| 1332+00 TO 1347+00 | 73.9 | 277.8 | 62.8 | 158.2 | -95.4 | |
| 1347+00 TO 1352+70 | 43.8 | 169.6 | 37.3 | 132.4 | -95.1 | |
| TOTAL | 436.2 | 1628 | 370.8 | 2267.2 | -1896.4 | |

NOTE:

A THICKNESS OF 6 INCHES OF TOPSOIL STRIPPING SHALL BE USED FOR REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

PLAN NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED.)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR SHALL CALL STATE ELECTRICAL CONTRACTOR AT (773) 287-7600 TO LOCATE STATE OWNED FACILITIES.

THE CONTRACTOR SHALL CONSTRUCT PROJECT IN THE DIRECTION OF TRAFFIC

THE CONTRACTOR SHALL NOT STORE ANY MATERIAS IN THE GRASS MEDIAN

MIXTURE REQUIREMENTS

| ITEM | AC | TYPE | VOID | RAP | % |
|--|----|-------|-------------|-----|---|
| BITUMINOUS SHOULDER, SUPERPAVE, 10" | PG | 58-22 | 2% @ 30 GYR | 50 | |

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION | | | NSPORTATION | |
|-----------|-----|---------------------------------------|------------|--------|------------------|--|
| NAME D | ATE | | | | | |
| | | | INTERST | ATE 55 | 5 | |
| 11_ | | MITERIOR CO | | | | |
| | | ILLERY AT ALLERSA | | | | |
| | | INDEX OF SHEETS | | | | |
| | | | HADEA OF | OHLL | | |
| | | | | AT | D 4 D D O | |
| ì | - 1 | HSI | T OF STATE | SIAN | DARDS | |
| | | | | • | | |
| j j | - 1 | | DIARI R | IOTEC | | |
| | | | PLAN N | MIE9 | | |
| .1 | | | | | | |
| | | VERT. | | | | |
| | SC/ | LE: | : NONE | | DRAWN BY: HMO | |
| | 300 | "LL" HORIZ. | | | DITAMIN DIS IMMO | |
| | | | | | | |
| | DA | l Ł | | | CHECKED BY: | |
| | | | | | | |