

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 344	2005-016PCC-PP	LAKE	14	6

SOUTHBOUND US RTE. 45

CONTRACT 62939

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
1	10+14	6 x 12	8.0	II	6 x 12	8.0	II
2	10+45	16 x 12	21.3	III	16 x 12	21.3	III
*3	10+96	6 x 12	8.0	II	6 x 12	8.0	II
4	11+51	6 x 12	8.0	II	6 x 12	8.0	II
5	11+96	19 x 12	25.3	IV	19 x 12	25.3	IV
6	12+42	6 x 12	8.0	II	6 x 12	8.0	II
7	12+60	6 x 12	8.0	II	6 x 12	8.0	II
8	13+07	6 x 12	8.0	II	6 x 12	8.0	II
9	13+50	6 x 12	8.0	II	13 x 12	17.3	III
10	13+90	6 x 12	8.0	II	6 x 12	8.0	II
11	14+45	17 x 12	22.7	III	17 x 12	22.7	III
12	15+12	6 x 12	8.0	II	6 x 12	8.0	II
13	15+79	13 x 12	17.3	III	6 x 12	8.0	II
14	16+04	13 x 12	17.3	III	13 x 12	17.3	III
15	16+50	6 x 12	8.0	II	6 x 12	8.0	II
16	17+00	39 x 12	52.0	IV	9 x 12	12.0	II
17	17+57	6 x 12	8.0	II	6 x 12	8.0	II
18	18+04	6 x 12	8.0	II			
19	18+59	6 x 12	8.0	II	6 x 12	8.0	II
20	18+82	23 x 12	30.7	IV	6 x 12	8.0	II
21	19+15	6 x 12	8.0	II			
22	19+50	10 x 12	13.3	II	6 x 12	8.0	II
23	19+95	13 x 12	17.3	III	13 x 12	17.3	III
24	20+50	11 x 12	14.7	II	11 x 12	14.7	II
25	21+00	10 x 12	13.3	II	10 x 12	13.3	II

***NOTE: DETECTOR LOOPS LOCATED AT STA. 11+00 SB WILL BE REPLACED DURING PATCHING LOCATION #3**

- Centerline of Hickory St. : Sta. 19+09
- Centerline of EJ&E bridge : Sta. 15+68
- Mundelein Firestation Access begins at Sta. 20+95 and ends at Sta. 21+90

NORTHBOUND US RTE 45

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE
**26	21+00				60 x 12	80.0	IV
27	19+53	6 x 12	8.0	II	6 x 12	8.0	II
28	19+49	6 x 12	8.0	II	6 x 12	8.0	II
29	19+39				6 x 12	8.0	II
30	18+60	17 x 12	22.7	III	17 x 12	22.7	III
31	17+55	6 x 12	8.0	II	6 x 12	8.0	II
32	17+00	6 x 12	8.0	II	6 x 12	8.0	II
33	16+45	6 x 12	8.0	II	6 x 12	8.0	II
34	16+00	6 x 12	8.0	II	6 x 12	8.0	II
35	15+16	6 x 12	8.0	II	6 x 12	8.0	II
36	14+63	6 x 12	8.0	II	6 x 12	8.0	II
37	14+48	6 x 12	8.0	II	6 x 12	8.0	II
38	13+89	6 x 12	8.0	II	6 x 12	8.0	II
39	13+65	6 x 12	8.0	II	6 x 12	8.0	II
40	13+47	10 x 12	13.3	II	10 x 12	13.3	II
41	13+03	9 x 12	12.0	II	6 x 12	8.0	II
42	12+60	6 x 12	8.0	II	6 x 12	8.0	II
43	11+96	6 x 12	8.0	II	6 x 12	8.0	II
44	11+50	6 x 12	8.0	II	6 x 12	8.0	II
45	11+00	13 x 12	17.3	III	13 x 12	17.3	III
46	10+57	6 x 12	8.0	II	6 x 12	8.0	II

****NOTE: C&G WILL BE REPLACED NEXT TO PATCHING LOCATION #26 AND ALSO 40 FT FROM STA. 10+00 TO 10+40 ON NB.**

ILLINOIS DEPARTMENT OF TRANSPORTATION
**US ROUTE 45
PAVEMENT PATCHING SCHEDULE**