



BAR SPLICER ASSEMBLY ALTERNATIVES

\*\* Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.



## INSTALLATION AND SETTING METHODS

"A" :Set bar splicer assembly by means of a template bolt. "B" :Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E) : Indicates epoxy coating.



CONTRACT NO. 68437 COUNTY TOTAL SHEET SHEETS NO. RTE. SECTION 404 D4 BRIDGE REP. WARREN 20 20 STA. 459+08.81 TO STA.460+84.25 FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT

## **NOTES**

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for

reinforcement bars. Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

Minimum Capacity =  $1.25 \times fy \times A_t$ (Tension in kips)


Minimum \*Pull-out Strength =  $1.25 \times fs_{ollow} \times A_t$ (Tension in kips)

Where fy = Yield strength of lapped reinforcement bars in ksi.

fs<sub>allow</sub>= Allowable tensile stress in lapped reinforcement bars in ksi (Service Load) A<sub>t</sub> = Tensile stress area of lapped reinforcement bars. \* = 28 day concrete

	BAR SPLIC	ER ASSEMBLI	ES	
Bar Size to be Spliced	Daviel Bar Length	Strength Requirements		
		Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension	
#4	1'-8''	14.7	5.9	
#5	2'-0"	23.0	9.2	
#6	2'-7"	33.1	13.3	
#7	3′-5″	45.1	18.0	
#8	4'-6''	58.9	23.6	
#9	5′-9″	75.0	30.0	
#10	7′-3′′	95.0	38.0	
#11	9'-0"	117.4	46.8	

Bar splicer assemblies shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."



## STANDARD

Bar Size	No. Assemblies Required	Location
#7	36	Deck
#6	24	Abutment
#6	20	End diaphragms

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION		
NAME	DATE	ALLENDED WILLIAM ST.		
		BAR SPLICER		
		DETAIL		
		SCALE: VERT. DRAWN BY CEJ DATE 05-05-2005 CHECKED BY		

DATE NAME SCALE

Min. Pull-out Strength = 9.2 kips - tension No. Required = Q