FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-6K-1	ST. CLAIR	188	18

CONTRACT NO.: 76815

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
US 50	CU YD.		CU YD.	CU YD.
48+50 TO 68+00	231	173	1061	-888
SE RAMP				
0+00 TO 9+00	300	225	456	-231
NE RAMP				
1+00 TO 12+50	248	186	599	-413
NW RAMP				
0+00 TO 16+50	81	61	1878	-1817
SW RAMP				
1+00 TO 14+00	21	16	16	0
TOTALS	881	661	4010	-3349

AGGREGATE BASE COURSE, TYPE A

LOCATION		AGGREGATE BASE COURSE, TYPE A (TON)
STA	STA	
HWY 50		
61+00	65+32	215
66+30	MEDIAN	47
SE RAMP		
9+30	MEDIAN	12
NW RAMP		
14+82.74	15+52	223
	TOTAL	497

AGGREGATE SHOULDERS, TYPE B

LOCATION			AGG. SHOULDERS, TYPE B (TONS)
STA	STA	LT/RT	
HWY 50			
67+36.80	68+36.00	LT	2.4
NW RAMP			
0+00	4+00	LT & RT	24.9
4+00	9+50	LT & RT	34.2
9+50	15+50	LT & RT	63.0
15+50	17+20	LT	5.6
SW RAMP			
1+38	2+00	LT	2.0
2+00	8+00	LT & RT	38.0
8+00	14+10.29	LT & RT	38.0
NE RAMP			
0+40	2+00	LT & RT	24.0
2+00	8+00	LT & RT	63.1
8+00	12+50.04	LT & RT	36.0
SE RAMP			
-0+14	2+00	LT & RT	13.3
2+00	8+00	LT & RT	57.0
8+00	9+65	LT & RT	9.0
		TOTAL	410.5

BITUMINOUS SURFACE REMOVAL 2 1/2"

LOCATION		BITUMINOUS SURFACE REMOVAL 2 1/2" (SQ YD)
STA	STA	
HWY 50		
47+00	48+57.18	1500
	TOTAL	1500

COMBINATION CURB & GUTTER REMOVAL

LOCATION			COMBO. CURB & GUTTER REMOVAL (FOOT)
STA	STA	LT/RT	
HWY 50			
66+13	66+92	BOTH	165
SE RAMP			
9+28.20	9+44.82	RT	50
		TOTAL	215

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

LOCATION			CCC&G TYPE B-6.24 (FOOT)
STA	STA	LT/RT	
HWY 50			
48+57.18	51+87.31	RT	330.3
52+95.17	57+82.4	RT	487.2
NW RAMP			
15+52	17+10	RT	200
ISLAND			45
SW RAMP			
0+42	1+67	RT	150
0+66	1+14	LT	63
SE RAMP			
8+42.50	9+50	RT	153
ISLAND			49
		TOTAL	1477.5

CLASS SI CONCRETE (OUTLET)

LOCATION			CLASS SI CONC. (OUTLET) (CU YD)
STA	STA	LT/RT	
SW RAMP			
1+13.65	1+65.62	LT	4.7
1+67.15	2+18	RT	4.6
SE RAMP			
7+59.50	8+42.50	RT	6.7
		TOTAL	16.0

CONCRETE MEDIAN SURFACE, 4 INCH

LOCATION	CONC. MEDIAN SURFACE, 4 INCH (SQ FT)
HWY 50	
STA. 66+31 TO STA. 66+91.93	670
NW RAMP	
LARGE ISLAND	2,095
SMALL ISLAND	315
SE RAMP	
SMALL ISLAND	270
TOTAL	3,350

MEDIAN REMOVAL

LOCATION			MEDIAN REMOVAL (SQ FT)
STA	STA	LT/RT	
HWY 50			
61+00	65+31.18	LT	2,980
66+13	66+91.73	BOTH	990
SE RAMP			
9+28.15	9+44.80	RT	120
		TOTAL	4,090

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAI ROUTE 64
SECTION 82-6K-1
ST. CLAIR COUNTY

DRAWN BY:

PLOT DATE: 7/1/2005

PLAN
NOTE BOOK NO.
SURVEYED
R.O.T.B.P.
ALIGNMENT CHECKED
RT. OF WAY CHECKED
CADD FILE NAME
BY
DATE

$$DATE$$
7/1/2005
$$$$
$$$$
$$$$