FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-6K-1	ST. CLAIR	188	19

CONTRACT NO.: 76815

BITUMINOUS PAVEMENT SCHEDULE

LOCATION STA.	LOCATION STA.	BIT. CONC. SURFACE COURSE SUPERPAVE (TONS)	LEVELING BINDER, SUPERPAVE (TONS)	BIT. CONC. BINDER COURSE SUPERPAVE, IL 19.0, N90 13 3/4" (SQ YD)	BIT. MATERIALS (PRIME COAT) (TONS)	AGGREGATE (PRIME COAT) (TONS)	BIT. SHOULDERS SUPERPAVE 8" (SQ YD)	BIT. SHOULDERS SUPERPAVE (TONS)
HWY 50								
47+00	50+00	243.3	162.2	125.0	3.02	4.35	91.0	50.4
50+00	56+00	452.0	300.8	840.0	3.20	6.77		49.2
56+00	62+00	95.0	63.2	190.0	0.72	1.40		26.0
62+00	68+00	376.7	251.1		1.68	6.76		120.0
68+00	68+36	20.0	13.3		0.82	0.36		8.0
NW RAMP								
0+00	4+00	60.0	40.0		0.36	1.08		65.0
4+00	9+50	83.5	55.7		0.51	1.51		90.0
9+50	15+50	223.3	149.0	544.0	1.04	3.99	295.0	56.1
15+50	17+17.73	120.1	80.1	829.0	0.45	2.14	85.0	
SW RAMP								
0+56.28	2+00	40.0	26.7	173.0	0.20	0.71		6.0
2+00	8+00	90.0	60.0		0.54	1.62		95.2
8+00	14+00	91.0	60.5		0.54	1.62		95.2
14+00	14+10.29	1.5	1.0		0.01	0.03		1.6
NE RAMP								
0+40	2+00	63.3	42.2	277.0	0.26	1.14	170.0	3.7
2+00	8+00	147.2	98.1	727.0	0.77	2.62	420.0	39.2
8+00	12+50.04	73.0	48.6	69.0	0.42	1.27	125.0	55.5
SE RAMP								
-0+14	2+00	32.0	21.3		0.20	0.60		34.0
2+00	8+00	136.0	90.6	567.0	0.72	2.45	315.0	53.0
8+00	9+65	80.0	52.7	347.0	0.33	1.40	64.0	7.7
TOTALS		2427.9	1617.1	4688.0	15.79	41.82	1565.0	855.8

LIME MODIFIED SOIL SCHEDULE

LOCATION STA	LOCATION STA	LT/RT	PROCESSING ~~LIME~~ MODIFIED SOIL 12" (SQ YD)	WATER (UNIT)	LIME (TON)
HWY 50					
48+57.23	50+00	RT	180	2.7	3.5
50+00	56+00	RT	1215	18.2	23.4
56+00	57+86	RT	260	3.9	5.0
NW RAMP					
10+90.58	15+50	LT	641	9.6	12.3
14+35.95	15+50	RT	100	1.5	1.9
15+50	17+20	LT	300	4.5	5.8
15+50	17+20	RT	800	12.0	15.4
NE RAMP					
0+47	2+00	RT	315	4.7	6.1
0+47	1+49.75	LT	68	1.0	1.3
2+00	8+00	RT	980	14.7	18.9
8+00	9+79.60	RT	180	2.7	3.5
SE RAMP					
3+68.87	8+00	RT	750	11.3	14.4
8+00	9+55	RT	540	8.1	10.4
		TOTAL	6329	94.9	121.8

PAVED SHOULDER REMOVAL

LOCATION STA	LOCATION STA	LT/RT	PAVED SHOULDER REMOVAL (SQ YD)
HWY 50			
48+57.18	51+87.31	RT	181
50+00	50+78.7	LT	97
52+95.37	57+85.7	RT	578
NW RAMP			
10+90.58	17+17.75	LT	352
14+35.95	17+17.75	RT	339
SW RAMP			
0+30	1+67.15	RT	95
0+52.3	1+13.65	LT	41
NE RAMP			
0+77.37	1+49.75	LT	53
0+21.44	9+79.60	RT	664
SE RAMP			
3+42.6	9+53.85	RT	581
8+91	9+53.85	LT	63
		TOTAL	3,044

PLAN | SURVEYED | PLOTTED | NOTE BOOK | CADD FILE NAME | DRAWN | CHECKED | QUANT. CHECKED | DATE | BY | NO. | REVISIONS

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAI ROUTE 64
SECTION 82-6K-1
ST. CLAIR COUNTY

DRAWN BY:

PLOT DATE: 7/1/2005

$$DATE$$
7/1/2005
n:\projects\ed05904\plan\pl-05904x.dgn
$$USER$$
$$REF$$