

SIGNING SCHEDULE

FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-6K-1	ST. CLAIR	188	22

CONTRACT NO.: 76815

LOCATION			EXISTING SIGN DESCRIPTION				REMOVE SIGN PANEL		RELOCATE SIGN PANEL ASSEMBLY		RELOCATE SIGN PANEL		SIGN PANEL		METAL POST	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT
STA	OFFSET TO EDGE OF SIGN PANEL	NOTES	POST TYPE	NUMBER	MESSAGE	TYPE 1 SQ FT	TYPE 3 SQ FT	TYPE A EACH	TYPE B EACH	TYPE 1 SQ FT	TYPE 3 SQ FT	TYPE 1 SQ FT	TYPE 3 SQ FT	TYPE A FT	FT	FT	EACH	
US 50																		
47+96.3	49.5	LT	REMAIN IN PLACE	METAL	O'FALLON													
48+14.8	49.5	LT	REMAIN IN PLACE	METAL	DRUNK DRIVER													
49+56.7	65.7	RT	REMOVE	METAL	R3-7R	RIGHT LANE MUST TURN RIGHT, 2.5' X 2.5'	6.25											
48+57.1	55.3	RT	NEW	WOOD	R3-1100R	RIGHT TURN LANE, 2' X 2'						4			14			
49+36.7	52.6	LT	REMAIN IN PLACE	WOOD	R2-1	SPEED LIMIT 45, 2' X 2.5'												
50+72.1	59.1	RT	REMOVE & RE-ERECT	WOOD	M3-41/MI-1/MI-4/M6-31 & M3-21/MI-1/MI-4/M5-1R1	WEST/64/50/STRAIGHT & EAST/64/50/RIGHT			1						18.5			
50+02.3	67.7	RT	RE-ERECTED SIGN															
51+51.4	0.6	RT	REMAIN IN PLACE	METAL	R4-7	KEEP RIGHT, 2' X 2.5'												
52+03.3	63.5	RT	REMOVE & RE-ERECT	BREAK-AWAY WIDE FLANGE	INTERSTATE GUIDESIGN	64-50 WEST/EAST ST LOUIS/STRAIGHT & 64-50 EAST/MT VERNON/RIGHT, 20' X 14.5'					290							
52+03.6	76.8	RT	RE-ERECTED SIGN															
53+00.8	64.8	LT	REMOVE & RE-ERECT	BREAK-AWAY WIDE FLANGE	INTERSTATE GUIDESIGN	64-50 EAST/MT VERNON/LEFT, 18' X 7.5'					135							
53+00.8	62	LT	RE-ERECTED SIGN															
53+22.3	52.2	RT	NEW	WOOD	W9-1R	RIGHT LANE ENDS, 2.5' X 2.5'						6.25			14.5			
53+73.8	5.7	RT	REMAIN IN PLACE	METAL	R4-7	KEEP RIGHT, 2' X 2.5'												
54+49.5	50.2	RT	REMOVE & RE-ERECT	WOOD	R2-1	SPEED LIMIT 45, 2' X 2.5'				5					14.5			
54+49.8	52	RT	RE-ERECTED SIGN															
55+46.8	52.5	RT	NEW	WOOD	W4-2R	LANE REDUCTION TRANSITION, 3' X 3'						9			14.5			
55+87.1	58.4	RT	REMOVE & RE-ERECT	WOOD	M3-41/MI-1/MI-4/M5-1L1	WEST/64/50/LEFT			1							13.5		1
55+87.1	5.8	RT	RE-ERECTED SIGN															
59+47.3	5.9	LT	RE-ERECTED SIGN FROM 60+21.3	METAL	R3-1100L	LEFT TURN LANE, 2' X 2'				4						9		1
58+57.5	4.8	LT	REMOVE & RE-ERECT	METAL	R3-1100L	LEFT TURN LANE, 2' X 2'												
59+71.7	7.2	LT	RE-ERECTED SIGN FROM 65+21.4	METAL	R4-7	KEEP RIGHT, 2' X 2.5'				5						9.5		1
60+21.3	4.6	RT	REMOVE & RE-ERECT @ 57+96.8	METAL	R3-1100L	LEFT TURN LANE, 2' X 2'												
62+91.3	58.2	LT	REMAIN IN PLACE	WOOD	M3-21/MI-1/MI-4/M5-1L1	EAST/64/50/LEFT												
65+21.4	7.7	LT	REMOVE & RE-ERECT @ 59+71.7	METAL	R4-7	KEEP RIGHT, 2' X 2.5'												
65+74.2	56.5	RT	REMOVE & RE-ERECT	BREAK-AWAY WIDE FLANGE	INTERSTATE GUIDESIGN	64-50 WEST/EAST ST LOUIS/LEFT, 20' X 7.5'					150							
65+75.1	62.4	RT	RE-ERECTED SIGN															
67+07.6	72.8	LT	REMOVE & RE-ERECT	BREAK-AWAY WIDE FLANGE	INTERSTATE GUIDESIGN	64-50 EAST/MT VERNON/STRAIGHT & 64-50 WEST/EAST ST LOUIS/RIGHT, 20' X 14.5'					290							
67+07.6	75.6	LT	RE-ERECTED SIGN															
68+36.1	48.2	RT	REMAIN IN PLACE	METAL	R3-1100R	RIGHT TURN LANE, 2' X 2'												

CONTINUED NEXT SHEET

PLAN	NO.	DATE
REVISED		
NOTED		
APPROVED		
ALIGNMENT CHECKED		
FILE NAME		

7/1/2005  
 c:\p06\p06a\vd06901.pln\p06901.dgn  
 \*REF\*  
 \*REF\*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAI ROUTE 64  
 SECTION 82-6K-1  
 ST. CLAIR COUNTY  
 DRAWN BY:

PLOT DATE: 7/1/2005