

SIGNING SCHEDULE (CONT.)

FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-6K-1	ST. CLAIR	188	23

CONTRACT NO.: I6815

NW RAMP																		
11+40.	25	LT	REMOVE & RE-ERECT, USE EXISTING POST	METAL		2 PART SIGN - PRAIRIE PLANTS & NO SPRAYING/NO MOWING			1									
12+50.	45	LT	REMOVE & RE-ERECT	WOOD		2 PART SIGN - WILDFLOWERS/ILLINOIS & PATRICIA BLAGJEVICH/FIRST LADY			1								16	
13+45.			NEW	SIGN TRUSS		SEE DETAIL SHEETS						400						
14+43.8	43.9	RT	REMOVE	BREAK-AWAY WIDE FLANGE		0'FALLON, LEFT ARROW, 13.5' X 3.5'		47.25										
15+04.3	32.1	RT	REMOVE & RE-ERECT	METAL	R8-3a	NO PARKING SYMBOL, 2' X 2'			4								12.5	
15+04.4	41.8	RT	RE-ERECTED SIGN															
15+43.3	40.9	RT	REMOVE & RE-ERECT	WOOD	R5-1a	WRONG WAY, 2' X 3'			6								14	
15+43.3	43.1	RT	RE-ERECTED SIGN															
15+44.3	40.1	LT	REMOVE & RE-ERECT	WOOD	R5-1a	WRONG WAY, 2' X 3'			6								14	
15+44.3	47	LT	RE-ERECTED SIGN															
16+39.8	41.2	RT	REMOVE & RE-ERECT	WOOD	R5-1	DO NOT ENTER, 2.5' X 2.5'			6.25								14.5	
16+40.	63.6	RT	RE-ERECTED SIGN															
16+47.9	39.6	LT	REMOVE & RE-ERECT	WOOD	R5-1	DO NOT ENTER, 2.5' X 2.5'			6.25								14.5	
16+47.9	47.25	LT	RE-ERECTED SIGN															
16+40.1	88.5	RT	NEW	WOOD	R1-2	YIELD			3.9								14.5	
16+75.2	73.8	RT	NEW	WOOD	R1-2	YIELD			3.9								14.5	
16+88.5	60	LT	REMOVE & RE-ERECT, USE EXISTING POST	METAL		2 PART SIGN - PRAIRIE PLANTS & NO SPRAYING/NO MOWING			1									
SW RAMP																		
1+67.2	5	RT	RE-ERECTED SIGN	METAL	R8-3	NO PARKING, 2' X 2.5'			5								13	
1+69.6	11	RT	REMOVE & RE-ERECT															
NE RAMP																		
1+49.6	31.3	RT	NEW	WOOD	W9-1R	RIGHT LANE ENDS, 2.5' X 2.5'						6.25					14.5	
1+59.5	12.2	RT	REMOVE & RE-ERECT	METAL	R8-3	NO PARKING, 2' X 2.5'			5								13	
2+41.3	31	RT	RE-ERECTED SIGN															
4+92.4	14.2	RT	REMOVE & RE-ERECT @ 5+96.7	METAL	R8-3a	NO PARKING SYMBOL, 2' X 2'												
4+96.3	31.6	RT	NEW	WOOD	W4-2R	LANE REDUCTION TRANSITION, 3' X 3'					9						15	
5+96.7	28.6	RT	RE-ERECTED SIGN FROM 4+92.4	METAL	R8-3a	NO PARKING SYMBOL, 2' X 2'			4								12.5	

CONTINUED NEXT SHEET

REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINALS

LOCATION		REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL EACH	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL TYPE 6 EACH
STA	LT/RT		
57+50	RT	1	
58+00	RT		1
TOTAL		1	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAI ROUTE 64
 SECTION 82-6K-1
 ST. CLAIR COUNTY
 DRAWN BY:

PLOT DATE: 7/1/2005

PLAN SURVIVED BY DATE
 PLOTTED BY DATE
 NOTE BOOK NO. OF MAY CHECKED
 NO. OF SHEETS CAD FILE NAME

DATE: 7/1/2005
 c:\p0\proj\826594\plan\p1\0606.dwg
 REF