FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-6K-1	ST. CLAIR	188	24
CONTRACT NO.: I6815				

SIGNING SCHEDULE (CONT.)

SE RAMP																		
6+87.9	26.2	RT	REMOVE & RE-ERECT	WIDE-FLANGE BREAK AWAY		O'FALLON/RIGHT ARROW, 13.5' X 3.5'						47.25						
6+87.2	41.3	RT	RE-ERECTED SIGN															
7+52.8	23.3	RT	REMOVE & RE-ERECT	WOOD	R5-1a	WRONG WAY, 2' X 3'					6				14			
7+52.8	39.3	RT	RE-ERECTED SIGN															
7+52.8	39.3	RT	NEW		R3-I100R	RIGHT TURN LANE, 2' X 2'												
8+15.2	39	RT	RE-ERECTED SIGN	METAL	R8-3a	NO PARKING SYMBOL, 2' X 2'					4			10.5				
8+15.2	14	RT	REMOVE & RE-ERECT															
8+74.9	33.6	LT	REMOVE & RE-ERECT	WOOD	R5-1	DO NOT ENTER, 2.5' X 2.5'					5				14.5			
8+75.9	26.2	LT	RE-ERECTED SIGN															
9+33.3	4.2	RT	REMOVE & RE-ERECT	WOOD	R6-2L	ONE WAY, 1.5' X 2'					3				14			
9+27.2	13.9	RT	RE-ERECTED SIGN															
			TOTALS				6.25	47.25	2	3	82.3	912.25	34.5	400	61.5	250	32	3

DELINEATOR SCHEDULE

LOCATION	STA	TO	STA	SINGLE WHITE EACH	SINGLE YELLOW EACH
NW RAMP	0+00		17+00	17	17
SW RAMP	1+00		14+00	13	13
NE RAMP	0+50		12+50	12	12
SE RAMP	0+00		9+00	9	9
SUB TOTAL				51	51
TOTAL				102	

SEEDING

LOCATION				SEEDING, CLASS 2A ACRE		NITROGEN POUND	PHOSPHORUS POUND	POTASSIUM POUND	MULCH, METHOD 2 ACRE	SEEDING, CLASS 4 (SPECIAL) ACRE	
	STA	TO	STA	LT	RT					LT	RT
US 50											
	47+00	TO	50+00	0.02	0.07	9	9	9	0.09		
	50+00	TO	56+00	0.03	0.29	32	32	32	0.32		
	56+00	TO	62+00	0.01	0.08	9	9	9	0.09		
	62+00	TO	68+36	0.04	0.08	12	12	12	0.12		
NW RAMP											
	0+00	TO	4+00	0.03	0.12	15	15	15	0.15		
	4+00	TO	9+50	0.07	0.32	39	39	39	0.39		
	9+50	TO	15+50	0.23	0.36	59	59	59	0.59	0.74	
	15+50	TO	17+55	0.09	0.12	21	21	21	0.21	0.12	
SW RAMP											
	0+00	TO	2+00	0.03	0.05	8	8	8	0.08		
	2+00	TO	8+00	0.03	0.04	7	7	7	0.07		
	8+00	TO	14+03	0.03	0.04	7	7	7	0.07		
NE RAMP											
	0+00	TO	2+00	0.03	0.11	14	14	14	0.14		
	2+00	TO	8+00	0.04	0.32	36	36	36	0.36		
	8+00	TO	12+50	0.02	0.12	14	14	14	0.14		
SE RAMP											
	-+14	TO	2+00	0.01	0.01	2	2	2	0.02		
	2+00	TO	8+00	0.09	0.26	35	35	35	0.35		
	8+00	TO	9+88	0.04	0.07	11	11	11	0.11		
SUBTOTAL				0.84	2.46	330	330	330	3.3	0.86	0.00
			TOTAL	3.30		330	330	330	3.3	0.86	

PAVEMENT REMOVAL

LOCATION			PAVEMENT REMOVAL (SQ YD)
STA	STA	LT/RT	
HWY 50			
61+00	61+31	LT	36
NW RAMP			
14+82.74	16+79.70	RT	157
16+86.27	17+09.01	RT	43
14+82.74	15+52	RT	30
SE RAMP			
9+10.45	9+44.55	RT	54
		TOTAL	320

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAI ROUTE 64
SECTION 82-6K-1
ST. CLAIR COUNTY

DRAWN BY:

PLOT DATE: 7/1/2005

PLAN		BY	DATE
SURVEYED 00/00/00			
ALIGNMENT CHECKED			
PT. OF INT. CHECKED			
NOTE BOOK			
NO.			